

HSR-Spaur 1-7 05-123-19312 - Planned WBD (P&A)

12-1/4" Surface Hole

7-7/8" Prod Hole

Existing

KB: 4870'

GL: 4860'

8 5/8", 24# Sfc Csg set @ 723'

Fox Hills Marker 1446'

Sussex Top @ 3993'

TOC 6260' CBL

Niobrara Top @ 6696'

Niobrara perms 6716'-6782'

Codell perms 7020' - 7040'

4 1/2" 11.6# Prod Csg @ 7164'

TD @ 7170' 2/14/1997

Planned

Welded Cap

Cement to surface

CIBP @ 80'

450 sk cmt plug 1650' - 520'

Cut 4 1/2 csg off @ 1550'

TOC ID 3632'

Top perf 3790'

CICR @ 3820'

Cement Plug 190 sx 4200'-3790'

Bottom perf 4200'

Cement Plug 25 sx 6660'-6260'

CIBP @ 6660'

