

From: [Craig Burger - DNR](#)
To: ["Haddock, Reed"; "Isac.Porraz@wpenergy.com"](#)
Cc: [David Andrews - DNR](#); [Jay Krabacher - DNR](#)
Subject: RE: RU 331-7 - Request to Defer CBL
Date: Tuesday, December 23, 2014 3:45:00 PM

Reed and Isac,

WPX can defer running the CBL on this well.

Just a reminder: the NTO requires monitoring the bradenheads of all wells on the pad until the CBL is run.

Thanks,

Craig Burger
Northwest Area Engineer



P 970.625.2497 Ext.2 | F 970.625.5682 | C 970-319-4194
796 Megan Ave., Suite 201, Rifle, CO 81650
craig_burger@state.co.us | www.colorado.gov/cogcc

From: Andrews - DNR, David [mailto:david.andrews@state.co.us]
Sent: Tuesday, December 23, 2014 8:38 AM
To: Craig Burger - DNR
Subject: Fwd: RU 331-7 - Request to Defer CBL

----- Forwarded message -----

From: **Haddock, Reed** <Reed.Haddock@wpenergy.com>
Date: Tue, Dec 23, 2014 at 8:32 AM
Subject: RU 331-7 - Request to Defer CBL
To: "Krabacher - DNR, Jay" <jay.krabacher@state.co.us>
Cc: David Andrews - DNR <david.andrews@state.co.us>, "Porraz, Isac" <Isac.Porraz@wpenergy.com>

Jay, Dave:

WPX Energy Rocky Mountain, LLC is requesting a CBL deferment on the Federal RU 331-7 located in the Section 7, T7S-R93W. Attached is a temperature survey that was performed after cementing the 4 ½" production casing on the subject well.

Information pertaining to the request is as follows:

Well:	Federal RU 331-7
API:	05-045-22349-00
Location:	Section 7 T7S-R93W
Surface Csg:	9 5/8" set and cemented at 1151'
Production Csg Cement Date:	4 ½" @ 10,254' – cemented 12/18/14

Cement: 1060 sks
Cement top from survey: 5400' Estimated
Estimated top of gas: 7279' Estimated
Estimated Top Perf: 7000' Estimated
Temp Survey: 12/18/14 Attached
Volume to fill annular: Hole remained full following cementing operations

Please let me know if you need additional information to approve this deferment.
After deferment is received, WPX Energy will continue to monitor the bradenhead pressure until the CBL has been performed and notify if pressure exceeds 150 psig.

12/18/2014	13:00	6 HR	0 BBL	0 PSI
12/18/2014	19:00	12 HR	0 BBL	0 PSI
12/19/2014	07:00	24 HR	0 BBL	0 PSI
12/20/2014	07:00	48 HR	0 BBL	0 PSI
12/21/2014	07:00	72 HR	0 BBL	0 PSI

Reed Haddock
Regulatory Specialist Staff
WPXENERGY
303-606-4086 (Office)
720-544-3267 (Cell)
Reed.Haddock@WPXEnergy.com