

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400759850

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 96850

Contact Name: GINA RANDOLPH

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 260-4509

Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

API Number 05-045-22359-00

County: GARFIELD

Well Name: Chevron

Well Number: GM 12-21

Location: QtrQtr: SENE Section: 20 Township: 6S Range: 96w Meridian: 6

Footage at surface: Distance: 2034 feet Direction: FNL Distance: 703 feet Direction: FEL

As Drilled Latitude: 39.511469 As Drilled Longitude: -108.125509

GPS Data:

Date of Measurement: 08/04/2014 PDOP Reading: 2.2 GPS Instrument Operator's Name: J. KIRKPATRICK

** If directional footage at Top of Prod. Zone Dist.: 1376 feet. Direction: FNL Dist.: 889 feet. Direction: FWL

Sec: 21 Twp: 6S Rng: 96W

** If directional footage at Bottom Hole Dist.: 1392 feet. Direction: FNL Dist.: 1011 feet. Direction: FWL

Sec: 21 Twp: 6S Rng: 96W

Field Name: GRAND VALLEY

Field Number: 31290

Federal, Indian or State Lease Number: COC24099

Spud Date: (when the 1st bit hit the dirt) 09/06/2014 Date TD: 09/12/2014 Date Casing Set or D&A: 09/12/2014

Rig Release Date: 09/13/2014 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 7361 TVD** 7033 Plug Back Total Depth MD 7302 TVD** 6974

Elevations GR 5575 KB 5596 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

RPM CBL MUDLOGS

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	60	22	0	60	VISU
SURF	13+1/2	9+5/8	32.3	0	1,085	305	0	1,085	VISU
1ST	8+3/4	4+1/2	11.6	0	7,347	1,120	3,850	7,347	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	2,240			NO	
MESAVERDE	4,122			NO	
CAMEO	6,772			NO	
ROLLINS	7,232			NO	

Comment:

Please note: The "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: GINA RANDOLPH

Title: PERMIT TECH II

Date: _____

Email: GINA.RANDOLPH@WPXENERGY.COM

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400759860	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400759859	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400759853	PDF-CBL 1ST RUN	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400759856	PDF-PULSED NEUTRON	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400759857	LAS-PULSED NEUTRON	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400759858	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400759861	WELLBORE DIAGRAM	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400759865	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)