

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: REYNOLDS 2-23

Project: COLORADO-WELD-NAD83-UTM13

Site: REYNOLDS 27-23 PAD

Rig name no.: BASIC 1549/1549

Event: ABANDONMENT

Start date: 10/15/2014

End date: 12/12/2014

Spud date: 3/23/2007

Active datum: RKB @4,942.00usft (above Mean Sea Level)

UWI: 0/3/N/68/W/23/0/NENE/6/0/N/283.000566/E/0/1082.002164/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	10/15/2014		MIRU Basic 1549. Kill well. ND well head. NU BOP. TOOH. RU Warrior. Run 3.81" gauge ring to 7170'. Set CIBP @ 7070'. Dump bail 2 sks cmt on CIBP. SI. SDFN.
2	10/16/2014		RU Warrior. Run CBL. Gas in fluid. TIH to 5000'. Circ well. TOOH. RU Warrior. Run CBL from 3700' to surf. TIH w/tbg to 7060'. RU Sanjel. Spot 30 sks Thermal 35 cmt from 7060' to 6554'. LD tbg to 4550'. Spot 50 sks G cmt from 4550' to 3892'. LD tbg. SI. SD
3	10/17/2014		RU Warrior & cut off csg @ 830'. Circ well. ND BOP. Unland csg. NU BOP. LD csg. TIH w/tbg to 930'. RU Sanjel. Spot 110 sks Type III cmt from 930' to 402'. ND. WOC. RU Warrior. Tag cmt top @ 402'. Set CIBP @ 80'. NU Test CIBP ND RDMO
4	12/12/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 83'. Filled casing stub with 31 bags 5000# cement. Capped casing with a metal plate containing well info. Backfilled.
5	12/12/2014		TIME : 12:00, ROUTE : W22, WINS: 92911, PROJECT TYPE: P&A, PROD: NB/CD, BATT#: 34003889, GATHERER: KMG, STATION: UNKNOWN, LINE : N/A, COMMENTS: P&A'd OFFLINE.