

Light, Cheryl

From: Diana Burn - DNR <diana.burn@state.co.us>
Sent: Tuesday, December 30, 2014 4:37 PM
To: Mallery, Josh
Cc: Sollee, Michael; Light, Cheryl; Mark Schlagenhauf - DNR; Barbara Westerdale - DNR; Penny Garrison - DNR
Subject: RE: Gee 37N-25HZX Sidetrack Info

Please proceed as proposed.

Thanks,
Diana

From: Mallery, Josh [mailto:Josh.Mallery@anadarko.com]
Sent: Tuesday, December 30, 2014 4:19 PM
To: diana.burn@state.co.us
Cc: Sollee, Michael; Light, Cheryl
Subject: Gee 37N-25HZX Sidetrack Info

Diana,

Upon tripping out at TD of the 8-3/4" Hole section on the Gee 37N-25HZ, only a portion of the mud motor was recovered and a fish was left downhole. We are requesting to open hole sidetrack the well and will target the same bottom hole location.

Gee 37N-25HZ well info:

- a. Well name and API – **Gee 37N-25HZ API# 05-123-39173-00**
- b. Explanation of situation and why you need to sidetrack - **Upon tripping out at TD of the 8-3/4" Hole section, only a portion of the mud motor was recovered and a fish was left downhole.**
- c. Total measured depth reached (also have TVD) - **7,578' MD / 7,181' TVD**
- d. Casing sizes set and measured depth - **9.625" @ 1,050' MD / 1,050' TVD**
- e. Description of fish-including top and bottom – **The top of the fish is the rotor from the mud motor, the bottom of the fish is the PDC bit, dimensions are as follows:**
 - **220" – rotor**
 - **57.8" - motor driveshaft**
 - **29.9" - bearing housing**
 - **10.7" - PDC bit**
 - **Fish total length 318.4" (26.53')**

- f. Type of cement you will be using including weight, yield, and sacks. – **This is an Open hole sidetrack, no cement.**
- g. Measured depth and TVD of sidetrack point - **7,293' MD / 7,126' TVD**
- h. Proposed target formation of sidetrack hole if different than permitted - **Remains a Niobrara target**
- i. BHL of sidetrack hole. Note if this is a change from permit - **BHL is unchanged, after the redrill of the curve the lateral will be drilled to plan**
- j. A hand drawing of wellbore including where cement will be, fish is, and sidetrack will be: **See Attachment**

Thanks,

Joshua Mallery
Wattenberg Drilling Engineer
Anadarko
O: 720-929-6632
C: 713-851-2298

[Click here for Anadarko's Electronic Mail Disclaimer](#)