

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: HSR-M. CHRISTINE 2-22

Project: COLORADO-WELD-NAD83-UTM13

Site: HSR-M. CHRISTINE 2-22

Rig name no.: KEY 104/104

Event: ABANDONMENT

Start date: 12/10/2014

End date: 12/23/2014

Spud date: 6/27/1990

Active datum: RKB @4,895.99usft (above Mean Sea Level)

UWI: 0/3/N/66/W/22/0/NENW/6/0/0/0/0/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	12/10/2014		MIRU SUMMIT SLICKLINE, RIH w/ PRESSURE BOMB TO 7228', FISH PLUNGER & BUMPER SPRING, TAG S.N. @ 7266', TAG TD @ 7399', RDMO SUMMIT SLICKLINE
2	12/11/2014		MIRU KEY 104, BLEED WELL DOWN, KILL WELL, NU BOP, RU FLOOR & TONGS, RELEASE PKR & TOO, LD PKR & TBG, ROUND TRIP BIT & SCRAPER TO 7050', SWI, DRAIN UP, SDFN
3	12/12/2014		RU WIRELINE, SET 4-1/2" CIBP @ 7030', RD WIRELINE, TIH, EOT @ 7020', TEST CIBP TO 1000PSI - HELD, RU CEMENTERS, PUMP 30SX OF 15.8# CLASS G CEMENT, TOO, LD TBG, SWI, DRAIN UP, SDFN
4	12/13/2014		RU WIRELINE, SHOOT HOLES @ 4560'-4561' & 4150'-4151', RD WIRELINE, TIH, SET 4-1/2" CIBP @ 4190', RU CEMENTERS, PUMP 180SX OF 15.8# CLASS G CEMENT, TOO, LD TBG, ROLL HOLE CLEAN @ 2000', TOO, LD TBG, SWI, DRAIN UP, SDFN
5	12/14/2014		RU WIRELINE, CUT CSG @ 1190', RD WIRELINE, CIRCULATE WELL, ND BOP, UNLAND CSG, NU BOP, RU FLOOR & TONGS, TOO, LD CSG, TIH w/ 2-3/8" TBG, EOT @ 1300', RU CEMENTERS, PUMP 370SX OF 14.8# TYPE 3 CEMENT, TOO, LD TBG, SWI, DRAIN UP, SDFN
6	12/15/2014		ND BOP, RU WIRELINE, RIH, TAG TOC @ 102', SET 8-5/8" CIBP @ 80', RD WIRELINE, TEST CIBP TO 1000PSI - HELD, RDMO KEY 104
7	12/23/2014		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 69'. Filled casing with 26 bags 5000# cement. Capped casing with a metal plate containing well info. Backfilled.
8	12/23/2014		TIME : 17:00, ROUTE : N15, WINS: 73925, PROJECT TYPE: P&A, PROD: NB/CD, BATT#: 36181683, GATHERER: KMG, STATION: 45190, LINE : N/A, COMMENTS: P&A'd OFFLINE.