



2122174

Krabacher - DNR, Jay <jay.krabacher@state.co.us>

## Re: GM 332-12 Low TOC (045-22467)

1 message

**Krabacher - DNR, Jay** <jay.krabacher@state.co.us>  
To: "Porraz, Isac" <Isac.Porraz@wpxenergy.com>  
Cc: "Haddock, Reed" <Reed.Haddock@wpxenergy.com>

Wed, Jan 7, 2015 at 10:39 AM

Isac:

Okay -- as you know, keep a close on the bradenhead-pressure. WPX has COGCC concurrence to conduct completions as planned on this well.

Jay Krabacher

On Wed, Jan 7, 2015 at 10:20 AM, Porraz, Isac <Isac.Porraz@wpxenergy.com> wrote:

Jay,

The GM 332-12 has a low production cement top. Please find the detailed information below:

Sec	Twn	Rng	Well	API	CBL TOC	Top of MVRD	Short*	Top of Gas	Approx. Planned Top Perf	Cmt over Perf	Bradenhead Press Before Completion
12	7S	96W	GM 332-12	05-045-22467	4,163	3,607	-756	4,680	4,690	527	0
*Note: Assuming 200' above MVRD for cement coverage											

There is adequate coverage above zones of interest, TOG, and planned top perf by 527 ft. We have good bond short of the MVRD 200 ft guideline, 756ft, with respect to our interpretation. We'd like to proceed with completion on this well, which is scheduled for Monday 1/19/2015. I've attached the CBL for your review. Please advise, thanks.

Isac J. Porraz

Petroleum Engineer



WPX ENERGY

1001 17th St, Suite 1200

Denver, CO 80202

(direct) 303-260-4521

(cell) 724-809-7647

isac.porraz@wpxenergy.com

--  
Jay Krabacher

N W Area Engineer



**COLORADO**  
Oil & Gas Conservation  
Commission

Department of Natural Resources

P 970.625.2497 x4

C 970.589.6180

796 Megan Ave., Suite 201, Rifle, CO 81650

jay.krabacher@state.co.us | [www.colorado.gov/cogcc](http://www.colorado.gov/cogcc)