

Noble Energy, INC  
State A36-1  
05-123-14719

### Proposed Wellbore Schematic

Re-enter and re-plug  
KB elev - 4633'  
GL elev - 4623'

\*\*Contact COGCC about isolating Sussex

Weld cap on 8.625" sur csg

8.625" surf csg set @ 302'

Base Fox Hills 326'

Deepest Water well: 600'

250 sk cmt plug set from 700' to surface

NO PROD CSG  
7.875" open hole to TD

30sxs cmt @ 6200'

TD = 6920'

R.O.  
4/9/2014