

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400762819			
Date Received: 01/02/2015			

SUNDRY NOTICE

Submit a signed original. This form is to be used for general, technical and environmental sundry information. For proposed or completed operations, describe in full in Comments or provide as an attachment. Identify Well by API Number; identify Oil and Gas Location by Location ID Number; identify other Facility by Facility ID Number.

OGCC Operator Number: <u>47120</u>	Contact Name <u>Cheryl Light</u>	Complete the Attachment Checklist OP OGCC
Name of Operator: <u>KERR MCGEE OIL & GAS ONSHORE LP</u>	Phone: <u>(720) 929-6461</u>	
Address: <u>P O BOX 173779</u>	Fax: <u>(720) 929-7461</u>	
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80217-3779</u> Email: <u>cheryl.light@anadarko.com</u>		
API Number : 05- <u>123</u> <u>29753</u> <u>00</u>	OGCC Facility ID Number: <u>300545</u>	Survey Plat
Well/Facility Name: <u>DOLPH</u>	Well/Facility Number: <u>9-1</u>	Directional Survey
Location QtrQtr: <u>SENE</u> Section: <u>1</u> Township: <u>2N</u> Range: <u>66W</u> Meridian: <u>6</u>		Srvc Eqpmt Diagram
County: <u>WELD</u> Field Name: <u>WATTENBERG</u>		Technical Info Page
Federal, Indian or State Lease Number: _____		Other

CHANGE OF LOCATION OR AS BUILT GPS REPORT

☐ Change of Location * ☐ As-Built GPS Location Report ☐ As-Built GPS Location Report with Survey

* Well location change requires new plat. A substantive surface location change may require new Form 2A.

SURFACE LOCATION GPS DATA Data must be provided for Change of Surface Location and As Built Reports.

Latitude _____ PDOP Reading _____ Date of Measurement _____
Longitude _____ GPS Instrument Operator's Name _____

LOCATION CHANGE (all measurements in Feet)

Well will be: _____ (Vertical, Directional, Horizontal)

Change of **Surface** Footage **From** Exterior Section Lines:

Change of **Surface** Footage **To** Exterior Section Lines:

Current **Surface** Location **From** QtrQtr SENE Sec 1

New **Surface** Location **To** QtrQtr _____ Sec _____

Change of **Top of Productive Zone** Footage **From** Exterior Section Lines:

Change of **Top of Productive Zone** Footage **To** Exterior Section Lines:

Current **Top of Productive Zone** Location **From** Sec 1

New **Top of Productive Zone** Location **To** Sec _____

Change of **Bottomhole** Footage **From** Exterior Section Lines:

Change of **Bottomhole** Footage **To** Exterior Section Lines:

Current **Bottomhole** Location Sec 1 Twp 2N

New **Bottomhole** Location Sec _____ Twp _____

Is location in High Density Area? _____

Distance, in feet, to nearest building _____, public road: _____, above ground utility: _____, railroad: _____,

property line: _____, lease line: _____, well in same formation: _____

Ground Elevation _____ feet Surface owner consultation date _____

FNL/FSL		FEL/FWL	
2102	FNL	610	FEL
Twp <u>2N</u>	Range <u>66W</u>	Meridian <u>6</u>	
Twp _____	Range _____	Meridian _____	
2102	FSL	511	FEL
Twp <u>2N</u>	Range <u>66W</u>		
Twp _____	Range _____		
2102	FSL	511	FEL
Twp _____	Range _____		
Twp _____	Range _____		

**

**

** attach deviated drilling plan

CHANGE OR ADD OBJECTIVE FORMATION AND/OR SPACING UNIT

<u>Objective Formation</u>	<u>Formation Code</u>	<u>Spacing Order Number</u>	<u>Unit Acreage</u>	<u>Unit Configuration</u>

OTHER CHANGES

☐ **REMOVE FROM SURFACE BOND** Signed surface use agreement is a required attachment

☐ **CHANGE OF WELL, FACILITY OR OIL & GAS LOCATION NAME OR NUMBER**

From: Name DOLPH Number 9-1 Effective Date: _____

To: Name _____ Number _____

☐ **ABANDON PERMIT: Permit can only be abandoned if the permitted operation has NOT been conducted. Field inspection will be conducted to verify site status.**

☐ WELL: Abandon Application for Permit-to-Drill (Form2) – Well API Number _____ has not been drilled.

☐ PIT: Abandon Earthen Pit Permit (Form 15) – COGCC Pit Facility ID Number _____ has not been constructed (Permitted and constructed pit requires closure per Rule 905)

☐ CENTRALIZED E&P WASTE MANAGEMENT FACILITY: Abandon Centralized E&P Waste Management Facility Permit (Form 28) – Facility ID Number _____ has not been constructed (Constructed facility requires closure per Rule 908)

OIL & GAS LOCATION ID Number: _____

☐ Abandon Oil & Gas Location Assessment (Form 2A) – Location has not been constructed and site will not be used in the future.

☐ Keep Oil & Gas Location Assessment (Form 2A) active until expiration date. This site will be used in the future.

Surface disturbance from Oil and Gas Operations must be reclaimed per Rule 1003 and Rule 1004.

☐ **REQUEST FOR CONFIDENTIAL STATUS**

☐ **DIGITAL WELL LOG UPLOAD**

☐ **DOCUMENTS SUBMITTED** Purpose of Submission: _____

RECLAMATION**INTERIM RECLAMATION**

☐ Interim Reclamation will commence approximately _____

Per Rule 1003.e.(3) operator shall submit Sundry Notice reporting interim reclamation is complete and site is ready for inspection when vegetation reaches 80% coverage.

☐ Interim reclamation complete, site ready for inspection.

Per Rule 1003.e(3) describe interim reclamation procedure in Comments below or provide as an attachment and attach required location photographs.

Field inspection will be conducted to document Rule 1003.e. compliance

FINAL RECLAMATION

☐ Final Reclamation will commence approximately _____

Per Rule 1004.c.(4) operator shall submit Sundry Notice reporting final reclamation is complete and site is ready for inspection when vegetation reaches 80% coverage.

☐ Final reclamation complete, site ready for inspection. Per Rule 1004.c(4) describe final reclamation procedure in Comments below or provide as an attachment.

Field inspection will be conducted to document Rule 1004.c. compliance

Comments:

ENGINEERING AND ENVIRONMENTAL WORK

☐ NOTICE OF CONTINUED TEMPORARILY ABANDONED STATUS

Indicate why the well is temporarily abandoned and describe future plans for utilization in the COMMENTS box below or provide as an attachment, as required by Rule 319.b.(3).

Date well temporarily abandoned _____ Has Production Equipment been removed from site? _____

Mechanical Integrity Test (MIT) required if shut in longer than 2 years. Date of last MIT _____

☐ SPUD DATE: _____

TECHNICAL ENGINEERING AND ENVIRONMENTAL WORK

Details of work must be described in full in the COMMENTS below or provided as an attachment.

☒ NOTICE OF INTENT Approximate Start Date 01/05/2015

☐ REPORT OF WORK DONE Date Work Completed _____

- | | | |
|----------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------|--------------------------------------------------------|
| <input type="checkbox"/> Intent to Recomplete (Form 2 also required) | <input type="checkbox"/> Request to Vent or Flare | <input type="checkbox"/> E&P Waste Mangement Plan |
| <input type="checkbox"/> Change Drilling Plan | <input checked="" type="checkbox"/> Repair Well | <input type="checkbox"/> Beneficial Reuse of E&P Waste |
| <input type="checkbox"/> Gross Interval Change | <input type="checkbox"/> Rule 502 variance requested. Must provide detailed info regarding request. | |
| <input type="checkbox"/> Other _____ | <input type="checkbox"/> Status Update/Change of Remediation Plans for Spills and Releases | |

COMMENTS:

- 1 No gyro needed.
- 2 Call AUTOMATION REMOVAL GROUP at least 24 hr prior to rig move. Request they isolate production equipment and remove any automation prior to rig MIRU.
- 3 MIRU WL. Retrieve bumper spring, RIH sinker bar, tag for fill.
- 4 Prepare location for base beam equipped rig. Install perimeter fence as needed.
- 5 Check and record Bradenhead pressure. If Bradenhead valve is not accessible, re-plumb so that valve is above GL.
- 6 MIRU, kill as necessary using clean fresh water with biocide. ND WH. NU BOP. Function test and document.
- 7 MIRU EMI services. TOO H tubing string, SB (consists of 238 jts 2-3/8" J55 4.7#/ft tubing), EMI while TOO H. Mark and replace any jts with >35% wall loss, record in OW jt number and depth. RDMO EMI services.
- 8 MIRU WL. PU and RIH gauge ring for 4-1/2" 11.6#/ft I80 casing to 7200'. RDMO WL.
- 9 PU and TIH RBP for 4-1/2" 11.6#/ft I80 casing, set at 7,150'. Roll hole using water containing biocide. PT plug to 1,000 psi for 15 min. If successful, dump 2 sx sand on RBP.
- 10 TOO H tubing string, SB.
- 11 ND BOP, ND TH. Remove topnut from surface casing head including packoff and plates if applicable.
- 12 Makeup handling sub for 4-1/2" casing if necessary. Unland 4-1/2" casing making sure to not exceed 129M lbs, remove slips, NU QDF on scsg head and dual entry flange.
- 13 NU BOP on annular side, function test and document. Ensure BOP has dies for 1-1/4" J55 tubing
- 14 PU and TIH 1-1/4" 2.33 #/ft J55 Integral Jt tubing to 1,125+/-' or as deep as possible. Ensure hoses are routed to allow returns from bradenhead.
- 15 Initiate circulation and make 2 sweeps of 1 gallon each Alcomer 74L while TIH. Continue to circulate annulus until clean returns and dead annular.
- 16 PUH 1 stand'.
- 17 MIRU Sanjel cementers. Spot 5bbl biocide water, 135 SX Control set C cement with 0.25 pps celloflake mixed to 13.5ppg and 1.74 cf/sk. Cement coverage designed for 1125' to 660'. Excess of 20% on 9" hole.
- 18 PUH to 550', circulate minimum 2x tubing volume or until returns clean using water containing biocide.
- 19 TOO H, LD tubing. RDMO cementers.
- 20 ND BOP, Dual entry flange and QDF, reland casing in slips, NU starting head/top nut.
- 21 NU tubing head on 4-1/2" casing.
- 22 NU BOP, function test and document. Ensure dies are 2-3/8" dies for production tubing.
- 23 Leave well shut in overnight.
- 24 Circulate any gas from hole using water containing biocide.
- 25 MIRU WL. PU and RIH CBL/CCL/VDL to 1500', log to surface (INCLUDE TRANSIT TIME ON LOG). Before proceeding, send log and discuss (Tyler.Hindman@anadarko.com). Also send logs and invoices to rscDJVendors@anadarko.com within 24hrs of completion. RDMO WL.
- 26 PU and TIH retrieving head on 2-3/8" tubing. TIH to RBP (7,150'+/-). Circulate sand off RBP, latch onto and release
- 27 TOO H with RBP, SB tubing, LD RBP.
- 28 TIH NC, XN, 238 jts 2-3/8" 4.7#/ft J55 tubing. If fill was encountered from slickline tag, tag up using tubing, circulate clean to PBMD.
- 29 Land tubing at 7529'+/-.
- 30 ND BOP, NU top flange, ensuring to use flanged master valve, XXH nipples and 5,000 psi rated casing valves. Ensure all components are rated to 5,000 psi.
- 31 RU hydrotester. Test from below tubing head, through master valve to 5,000 psi. RDMO hydrotester.
- 32 Broach tubing if time allows, notify foreman of completion. RDMO WO rig.

CASING AND CEMENTING CHANGES

Casing Type	Size	Of	/	Hole	Size	Of	/	Casing	Wt/Ft	Csg/LinTop	Setting Depth	Sacks of Cement	Cement Bottom	Cement Top

H2S REPORTING

Data Fields in this section are intended to document Sample and Location Data associated with the collection of a Gas Sample that is submitted for Laboratory Analysis.

Gas Analysis Report must be attached.

H2S Concentration: _____ in ppm (parts per million)

Date of Measurement or Sample Collection _____

Description of Sample Point:

Absolute Open Flow Potential _____ in CFPD (cubic feet per day)

Description of Release Potential and Duration (If flow is not open to the atmosphere, identify the duration in which the container or pipeline would likely be opened for servicing operations.):

Distance to nearest occupied residence, school, church, park, school bus stop, place of business, or other areas where the public could reasonably be expected to frequent: _____

Distance to nearest Federal, State, County, or municipal road or highway owned and principally maintained for public use: _____

COMMENTS:

Best Management Practices		
No	BMP/COA Type	Description

Operator Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cheryl Light
Title: Sr. Regulatory Analyst Email: DJRegulatory@anadarko.com Date: 1/2/2015

Based on the information provided herein, this Sundry Notice (Form 4) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: SCHLAGENHAUF, MARK Date: 1/11/2015

CONDITIONS OF APPROVAL, IF ANY:**COA Type****Description**

	The additional cement referenced shall be placed as indicated and comply with Rule 317.j. The placed cement shall be verified with a CBL and documented with a Form 5 Drilling Completion Report.
--	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

General Comments**User Group****Comment****Comment Date**

#Error		
--------	--	--

Total: 0 comment(s)

Attachment Check List**Att Doc Num****Name**

400762819	FORM 4 SUBMITTED
400762821	OTHER

Total Attach: 2 Files