

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: RAITH L 15-3

Project: COLORADO-WELD-NAD83-UTM13

Site: RAITH L 15-3

Rig name no.: CONCORD 6/6

Event: ABANDONMENT

Start date: 12/1/2014

End date:

Spud date: 1/8/1980

Active datum: RKB @4,872.00usft (above Mean Sea Level)

UWI: NE/NW/0/3/N/66/W/15/0/0/6/PM/N/990.00/W/0/1,590.00/0/0

Report no.	Report date	MD (usft)	24 hr summary
1	12/01/2014		MIRU Concord 6, TP/CP 200/200, SCP 0, blow down, kill, NU, TOO, RU Warrior Wireline, RIH gauge ring to 7800, Set CIBP @ 7724, Load and test to 500 PSI (OK), dump bail 2 SX CMT, RUN CBL from 7700 to 4000, gas in fluid, SI, SDFN
2	12/02/2014		RU Warrior WL, run CBL from 4500 to sur, Shot SQZ holes, 3 SPF, .6" Holes @ 7040', PUH shot 6 SPF .60" hole @ 6670, Set CIBP w/ 218 jts @ 6712, RU Sanjel, unable to est CIRC, pressure up to 3000 lost pressure, well on vac, TOO 100 jts, SI, SDFN
3	12/03/2014		Cont TOO, TIH w/ 3.875 rock bit, RU Power swivel, mill out CIBP, circ clean, Cont TIH tag CMT cap CIBP @ 7720, break circ, TOO SB, SI, SDFN
4	12/04/2014		TIH PKR, set w/ 232 jts @ 7144, PT to 3k-no test, TOO, RU Warrior Wireline, set 4.5 CIBP @ 7640, dump bail 2 SX CMT on top, shoot SQZ holes, 6 SPF .60" holes @ 7030 & 6670, TIH CIBP and 200 jts, SI, SDFN
5	12/05/2014		Set CIBP @ 6712, RU Sanjel, pump 4 bbl, 110 SX 50/50 POZ G, displace w/ 23 bb, TOO circ clean @ 4800, Cont TOO, RU Warrior Wireline, RIH shoot 3 SPF .60" holes @ 4620, PU shoot 6 SPF .60" @ 4220, SI, SDFN
6	12/08/2014		TIH, set CIBP @ 4249, RU Sanjel, pump 5 bbl, 20 bbl SMS, 5 bbl, 37 bbl (180 SX) 0-1-0 "G" CMT, disp 13.5 bbl, Sting out, TOO circ clean @ 3325, Cont TOO LD, RU Warrior Wireline, set CIBP @ 1700, TIH to CIBP, SI, SDFN
7	12/09/2014		RU Sanjel, pump 90 SX Type III, displace 1 bbl, TOO circ clean w/ 4 jts, WOC, RU Warrior Wireline, tag TOC @ 310, PU set 4.5" CIBP @ 80, PT to 1000 for 15 min, GOOD, RDMO
8	01/07/2015		Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 70' in 4-1/2", surface in 8-5/8. Filled casing stub with 10 bags 5000# cement. Capped casing with a metal plate containing well info. Backfilled.