

Document Number:
400776486

Date Received:

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set. A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 47120 Contact Name: REBECCA HEIM
 Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6361
 Address: P O BOX 173779 Fax: (720) 929-7361
 City: DENVER State: CO Zip: 80217- Email: REBECCA.HEIM@ANADARKO.COM

For "Intent" 24 hour notice required, Name: _____ Tel: _____
 Email: _____

COGCC contact: _____

API Number 05-123-07310-00 Well Number: 1
 Well Name: ESTHER F. GAUMER
 Location: QtrQtr: NESW Section: 21 Township: 3N Range: 66W Meridian: 6
 County: WELD Federal, Indian or State Lease Number: _____
 Field Name: WATTENBERG Field Number: 90750

Notice of Intent to Abandon Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.207030 Longitude: -104.785780
 GPS Data:
 Date of Measurement: 02/08/2006 PDOP Reading: 2.6 GPS Instrument Operator's Name: Steve Fisher
 Reason for Abandonment: Dry Production for Sub-economic Mechanical Problems
 Other _____
 Casing to be pulled: Yes No Estimated Depth: _____
 Fish in Hole: Yes No If yes, explain details below
 Wellbore has Uncemented Casing leaks: Yes No If yes, explain details below
 Details: _____

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
CODELL	7468	7488	12/17/2014	B PLUG CEMENT TOP	7410
J SAND	7885	7926	12/17/2014	B PLUG CEMENT TOP	7815

Total: 2 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	12+1/4	8+5/8	24	522	400	522	0	VISU
1ST	7+7/8	4+1/2	10.5	8,030	200	8,030	7,396	CBL
S.C. 1.1				7,340	160	7,341	6,620	CBL
S.C. 2.1				1,469	200	1,568	1,130	CBL
			Stage Tool	780	300	810	580	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 7815 with 2 sacks cmt on top. CIBP #2: Depth 7410 with 50 sacks cmt on top.
 CIBP #3: Depth 83 with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
 CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 60 sks cmt from 1568 ft. to 684 ft. Plug Type: CASING Plug Tagged:
 Set 185 sks cmt from 673 ft. to 130 ft. Plug Type: STUB PLUG Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
 Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:

Perforate and squeeze at 4600 ft. with 370 sacks. Leave at least 100 ft. in casing 4245 CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
 Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth

(Cast Iron Cement Retainer Depth)

Set _____ sacks half in. half out surface casing from _____ ft. to _____ ft. Plug Tagged:
 Set 31 sacks at surface
 Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: Yes No
 Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: 576 ft. of 4+1/2 inch casing Plugging Date: 01/16/2015
 *Wireline Contractor: PIONEER *Cementing Contractor: BAKER HUGHES
 Type of Cement and Additives Used: _____
 Flowline/Pipeline has been abandoned per Rule 1103 Yes No *ATTACH JOB SUMMARY

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: REBECCA HEIM
 Title: SR. REGULATORY ANALYST Date: _____ Email: rscdjpostdrill@anadarko.com

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Date: _____

CONDITIONS OF APPROVAL, IF ANY:

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
400776487	OPERATIONS SUMMARY
400776488	GYRO SURVEY
400776489	WELLBORE DIAGRAM
400776490	CEMENT JOB SUMMARY
400776493	WIRELINE JOB SUMMARY

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)