

FORM

6

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Replug By Other Operator

Document Number:

400779074

Date Received:

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 47120

Contact Name: CHERYL LIGHT

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6461

Address: P O BOX 173779

Fax: (720) 929-7461

City: DENVER State: CO Zip: 80217-

Email: CHERYL.LIGHT@ANADARKO.COM

For "Intent" 24 hour notice required,

Name: Carlile, Craig

Tel: (970) 629-8279

COGCC contact:

Email: craig.carlile@state.co.us

API Number 05-123-10152-00

Well Name: RUSCH

Well Number: 34-15

Location: QtrQtr: NWSE Section: 15 Township: 3N Range: 67W Meridian: 6

County: WELD

Federal, Indian or State Lease Number:

Field Name: WATTENBERG

Field Number: 90750

☒ Notice of Intent to Abandon☐ Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.221996

Longitude: -104.873213

GPS Data:

Date of Measurement:

PDOP Reading:

GPS Instrument Operator's Name:

Reason for Abandonment: ☐ Dry☐ Production for Sub-economic☐ Mechanical Problems☒ Other RE-ENTER AND PLUGCasing to be pulled: ☐ Yes☒ No

Estimated Depth:

Fish in Hole: ☒ Yes☐ No

If yes, explain details below

Wellbore has Uncemented Casing leaks: ☐ Yes☒ No

If yes, explain details below

Details: The well was originally drilled and abandoned 03/31/81 by MGF Oil Corp. Purpose is to reenter and adequately replug prior to hydraulic stimulation of proposed horizontal well per DJ Basin Offset Policy dated December 16, 2013.

"While drilling at 7106' surface casing parted. Subsequent attempts to tie back surface casing were unsuccessful." Well was plugged with reported 100 sacks of cement from 167' to surface. We will attempt to set a 12" surface casing over the existing 8-5/8" with a dual air rotary rig, attempt to tie back the 8-5/8" to surface and drill out cement and re-enter openhole to properly plug the well. The top of the Nio is 6825'

Current and Previously Abandoned Zones

Formation

Perf. Top

Perf. Btm

Abandoned Date

Method of Isolation

Plug Depth

Total: 0 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	12+1/4	8+5/8	24	200	180	200	80	CALC
OPEN HOLE	7+7/8			7,106				

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth _____ with _____ sacks cmt on top. CIBP #2: Depth _____ with _____ sacks cmt on top.
CIBP #3: Depth _____ with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set _____ 320 _____ sks cmt from _____ 7106 _____ ft. to _____ 6400 _____ ft. Plug Type: OPEN HOLE Plug Tagged: ☐
Set _____ 400 _____ sks cmt from _____ 4220 _____ ft. to _____ 3800 _____ ft. Plug Type: OPEN HOLE Plug Tagged: ☒
Set _____ _____ sks cmt from _____ _____ ft. to _____ _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ _____ sks cmt from _____ _____ ft. to _____ _____ ft. Plug Type: _____ Plug Tagged: ☐
Set _____ _____ sks cmt from _____ _____ ft. to _____ _____ ft. Plug Type: _____ Plug Tagged: ☐

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
(Cast Iron Cement Retainer Depth)

Set _____ 710 _____ sacks half in. half out surface casing from _____ 1000 _____ ft. to _____ 30 _____ ft. Plug Tagged: ☐

Set _____ 10 _____ sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☒ No

Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: _____ ft. of _____ inch casing Plugging Date: _____

*Wireline Contractor: _____ *Cementing Contractor: _____

Type of Cement and Additives Used: _____

Flowline/Pipeline has been abandoned per Rule 1103 ☐ Yes ☐ No *ATTACH JOB SUMMARY

Technical Detail/Comments:

- a. As-built well location GPS data will be submitted on the Form 6 Subsequent Report of Abandonment.
- b. Closed loop system will be used.
- c. Re-plug and re-entry procedure attached.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: SR. REGULATORY ANALYST Date: _____ Email: DJREGULATORY@ANADARKO.COM

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____ Expiration Date: _____

Attachment Check List

Att Doc Num

Name

400779078	SURFACE OWNER CONSENT
400779079	LOCATION PHOTO
400779080	PROPOSED PLUGGING PROCEDURE
400779081	WELLBORE DIAGRAM

Total Attach: 4 Files

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)