

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400728304

Date Received:

11/25/2014

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100185

Contact Name: Toby Sachen

Name of Operator: ENCANA OIL & GAS (USA) INC

Phone: (720) 876-5845

Address: 370 17TH ST STE 1700

Fax:

City: DENVER

State: CO

Zip: 80202-

API Number 05-123-39631-00

County: WELD

Well Name: Jillson-East Rinn

Well Number: 3E-22H-M268

Location: QtrQtr: SWSW Section: 22 Township: 2N Range: 68W Meridian: 6

Footage at surface: Distance: 374 feet Direction: FSL Distance: 711 feet Direction: FWL

As Drilled Latitude: 40.117907 As Drilled Longitude: -104.996241

GPS Data:

Date of Measurement: 10/17/2014 PDOP Reading: 2.1 GPS Instrument Operator's Name: Chris Bettencourt

** If directional footage at Top of Prod. Zone Dist.: 510 feet. Direction: FSL Dist.: 1027 feet. Direction: FWL

Sec: 22 Twp: 2n Rng: 68w

** If directional footage at Bottom Hole Dist.: 2542 feet. Direction: FSL Dist.: 967 feet. Direction: FWL

Sec: 15 Twp: 2n Rng: 68w

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 07/30/2014 Date TD: 08/08/2014 Date Casing Set or D&A: 08/11/2014

Rig Release Date: 10/13/2014 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 15167 TVD** 7517 Plug Back Total Depth MD 15148 TVD** 7517

Elevations GR 4953 KB 4966

Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, MWD

run on Jillson 14-22, 123-23027, 260' away.

No open hole logs on this pad. Induction log was

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	16	30	0	97	120	0	97	
SURF	12+1/4	9+5/8	40	0	888	351	0	902	
1ST	8+3/4	7	26	0	7,990	705	0	7,990	
2ND	6+1/8	4+1/2	13.5	0	15,150	665	4,576	15,150	

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	7,238				
NIOBRARA	7,340				
FORT HAYS	7,788				
CODELL	7,869				

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Toby Sachen

Title: Regulatory Analyst Date: 11/25/2014 Email: toby.sachen@encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400739861	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400739860	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400728304	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400739843	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400739854	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400739856	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400739858	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400739863	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)