

Attachment #1 – Wellbore Diagram

EnCana Oil & Gas (USA) Inc.	
Well : RUHL 1-32 Field : Wattenberg County : Weld County State : Colorado Surface : Lat: 40.0995450 Long: -104.5684200 : 990 FNL, 990 FEL, NENE Sec 32 T2N R64W API # : 05-123-10432 Grd Elev : 4995' GR KB Elevation: 5007' KB	
<u>Log Tops:</u> Fox Hills Base 992' Sussex 4556' Niobrara 6943' Codell 7177' J Sand 7627'	<div style="float: right; border: 1px solid black; padding: 5px; margin-bottom: 20px;">Well History: Spud 11/13/81 TD 11/20/81</div> <div style="clear: both;"></div> <div style="margin-top: 20px;"><u>Surface Casing</u> 8-5/8" Surface Casing set @ 229', cmt'd w/ 200 sx</div> <div style="margin-top: 20px;">TOC @ 6696' CBL dated 12/31/2014</div> <div style="margin-top: 20px;"><u>Production Casing</u> 4-1/2" production casing set @ 7774' Cmt w/ 275 sx</div> <div style="margin-top: 20px;"><u>Production Tubing</u> 240 jts 2-3/8" tubing Landed @ 7584' 12/31/2014</div> <div style="margin-top: 20px; text-align: right;"><u>J Sand Perfs</u> 7632-7665' Frac'd with 219,000 gal Versagel and 25,000# 100 Mesh, and 492,000# 20/40 sand (02/22/82)</div> <div style="text-align: center; margin-top: 20px;">TD 7785'</div>
Drawn by: Scott Reed	Date: 01/26/2015