

WELLBORE DIAGRAM

Directions: 0

Basywater Exploration

Moody 1-30

NENE Sec 30-T7N-R64W

SHL: 660 ft FNL & 660 ft FWL

Updated

1/20/2015

SMS

Weld County CO
05-123-12702

G.L.= 4846

K.B.= 4859

13

8-5/8" 24# @ 310 ft (12.25" OH)

Cmt'd w/ 250 sks Type II; circ to surface

TOC: ??? ft

CBL ???

<<

>>

Niobrara - 6960, 6966, 6971, 6976, 6978, 7027, 7034 & 7044 ft, 8 holes (1985)

Stimulate 6960-7148 ft w/ 106,000 gals XL, 15,000 lbs 100 mesh & 271,000 lbs 20/40 sand (1985)

<<

>>

Codell - 7121, 7127, 7144, 7148 ft, 4 holes (1985)

<<

>>

Codell - 7139-7153 ft, 4 spf, 56 holes (2/11/08)

Frac Codell 7139-7153 ft w/ 3156 bbls XL gel & 243,674 lbs 20/40 dn tbgs, pkr @ 7075 ft (2/14/08)

PBTD= 7,590'

4-1/2", 11.6# @ 7687 ft (7-7/8" OH)

TD MD= 7,690'

Cmt'd w/ 325 sks cmt

TD VD= 7,690'