

WELLBORE DIAGRAM

Directions: 0

Basywater Exploration

Andolsek 1-2

NWSW Sec 2-T6N-R65W

SHL: 1980 ft FSL & 660 ft FWL

Updated

1/26/2015

SMS

Weld County CO
05-123-12575

G.L.= 4840

K.B.= 4851

11

8-5/8" 24# @ 336 ft (12.25" OH)

Cmt'd w/ 230 sks cmt; circ to surface

TOC: 6362 ft
CBL 1985

<<

>>

Niobrara - 6879, 6875, 6873, 6988, 6994, 6999, 7005, 7055, 7063 & 7070 ft, 10 holes (1985)

Stimulate 6879-7168 ft w/ 106,000 gals XL, 15,000 lbs 100 mesh & 178,000 lbs 20/40 sand (1985)

<<

>>

Codell - 7134, 7147, 7159, 7162 & 7168 ft, 5 holes (1985)

<<

>>

Codell - 7157-7172 ft, 4 spf, 60 holes (2/14/08)

Frac Codell 7134-7172 ft w/ 3264 bbls XL gel & 249,020 lbs 20/40 dn tbgs, pkr @ 7102 ft (2/21/08)

PBTD= 7,602'

TD MD= 7,736'

TD VD= 7,736'

4-1/2", 11.6# @ 7700 ft (7-7/8" OH)

Cmt'd w/ 300 sks cmt