

# Wallace Currier 19-1

NE/NE - Section 19 - T10S - R95W

FEE / FEE

API: 05-077-08087

Lat. 39.178813/Long. -108.028061

Mesa County, Colorado

Current wellbore diagram.

Cement from 285' to surface.

9 5/8" - 40 lb. - J55  
Surface casing  
shoe @ 285'

2 3/8" - 4.7lb. - J-55  
Set @ 3100

Cement from 285' to surface.

Rollins, Cozette and  
Corcoran formation  
Perfs shot from  
3922' to 4504'

5 1/2" - 14 lb. J55  
Production casing  
shoe @ 4573'