

Well

:

MURATA 1-19J

Field

:

Wattenberg

County

:

Weld County

State :

Colorado

Surface

:

Lat: 40.1267780

Long: -104.8255380

:

1400 FNL, 1320 FWL CNW Sec 19 T2N R66W

API #

:

05-123-11644

Grd Elev

:

4858' GR

KB Elevation: 4868' KB

Log Tops:

Fox Hills Base

571'

Sussex

4401'

Niobrara

7099'

Codell

7382'

J Sand

7822'

Well History:	
Spud	02/25/84
TD	03/04/84

Surface Casing

8-5/8" Surface Casing set

@ 555', cmt'd w/ 450 sx

TOC @ 6310'

CBL dated 8/28/84

Production Casing

4-1/2" production casing set @ 8012'.

Cmt w/ 350 sx

Production Tubing

2-3/8" Tubing set @ 7840

244 jts (02/18/2010)

J Sand Perfs

7840-7875'

Frac'd with 4875 bbls and 100,000# 100

mesh and 580,000# 20/40 sand (12/10/84)

TD 8012'