

FORM  
5A

Rev  
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400786873

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322  
2. Name of Operator: NOBLE ENERGY INC  
3. Address: 1625 BROADWAY STE 2200  
City: DENVER State: CO Zip: 80202  
4. Contact Name: Eileen Roberts  
Phone: (303) 2284330  
Fax: (303) 2284286  
Email: eroberts@nobleenergyinc.com

5. API Number 05-123-37625-00  
6. County: WELD  
7. Well Name: ROHN STATE  
Well Number: LD10-64HN  
8. Location: QtrQtr: NESE Section: 9 Township: 9N Range: 58W Meridian: 6  
9. Field Name: WILDCAT Field Code: 99999

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 12/18/2014 End Date: 12/20/2014 Date of First Production this formation: 01/13/2015

Perforations Top: 6136 Bottom: 10038 No. Holes: 0 Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☐

Frac'd the Niobrara w/ 3779469 gals of Silverstim and Slick Water with 4063790#'s of Ottawa sand.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 89987 Max pressure during treatment (psi): 5808

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.69

Total acid used in treatment (bbl): 0 Number of staged intervals: 34

Recycled water used in treatment (bbl): 4458 Flowback volume recovered (bbl): 870

Fresh water used in treatment (bbl): 85528 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 4063790 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 01/20/2015 Hours: 24 Bbl oil: 372 Mcf Gas: 88 Bbl H2O: 719

Calculated 24 hour rate: Bbl oil: 372 Mcf Gas: 88 Bbl H2O: 719 GOR: 236

Test Method: FLOWING Casing PSI: 348 Tubing PSI: 547 Choke Size: 20/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1352 API Gravity Oil: 40

Tubing Size: 2 + 3/8 Tubing Setting Depth: 5928 Tbg setting date: 01/08/2015 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Eileen Roberts \_\_\_\_\_

Title: Regulatory Analyst I \_\_\_\_\_

Date: \_\_\_\_\_

Email: eroberts@nobleenergyinc.com \_\_\_\_\_

:

### **Attachment Check List**

<b><u>Att Doc Num</u></b>	<b><u>Name</u></b>
---------------------------	--------------------

--	--

Total Attach: 0 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>
--------------------------	-----------------------

<b><u>Comment Date</u></b>
----------------------------

--	--	--

Total: 0 comment(s)