

FORM
2
Rev
08/13

State of Colorado
Oil and Gas Conservation Commission
1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
400407730

APPLICATION FOR PERMIT TO:

Drill Deepen Re-enter Recomplete and Operate

Date Received:
06/11/2014

TYPE OF WELL OIL GAS COALBED OTHER _____
ZONE TYPE SINGLE ZONE MULTIPLE ZONES COMMINGLE ZONES

Refiling
Sidetrack

Well Name: GP-Dairy Well Number: 4-20-19
Name of Operator: MINERAL RESOURCES INC COGCC Operator Number: 57667
Address: PO BOX 328
City: GREELEY State: CO Zip: 80632
Contact Name: CLAYTON DOKE Phone: (720)420-5700 Fax: (720)420-5800
Email: cdoke@iptengineers.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20090133

WELL LOCATION INFORMATION

QtrQtr: NENE Sec: 20 Twp: 5N Rng: 65W Meridian: 6
Latitude: 40.389960 Longitude: -104.682510

Footage at Surface: 694 feet FNL/FSL FNL 1305 feet FEL/FWL FEL

Field Name: WATTENBERG Field Number: 90750
Ground Elevation: 4673 County: WELD

GPS Data:
Date of Measurement: 08/23/2013 PDOP Reading: 1.7 Instrument Operator's Name: C HOLMES

If well is Directional Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FNL 2181 FSL 966 FEL/FWL FEL 460 FSL 990
Bottom Hole: FNL/FSL FNL 990 FSL 460 FEL/FWL FEL
Sec: 20 Twp: 5N Rng: 65W Sec: 19 Twp: 5N Rng: 65W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: Fee State Federal Indian

The Surface Owner is: is the mineral owner beneath the location.
(check all that apply) is committed to an Oil and Gas Lease.
 has signed the Oil and Gas Lease.
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: Fee State Federal Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: _____ Surface Surety ID: _____

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Please see attached Mineral Lease Map

Total Acres in Described Lease: 20 Described Mineral Lease is: Fee State Federal Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 514 Feet

Building Unit: 514 Feet

High Occupancy Building Unit: 2721 Feet

Designated Outside Activity Area: 5280 Feet

Public Road: 305 Feet

Above Ground Utility: 467 Feet

Railroad: 473 Feet

Property Line: 264 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).

- Enter 5280 for distance greater than 1 mile.

- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.

- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: Buffer Zone
 Exception Zone
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit

- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.

- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 660 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 460 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

Proposed Spacing Unit: S/2 of Sec 19-T5N-R65W & SW/4 of Sec 20-T5N-R65W. PSU Map is attached.

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		480	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 15587 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 304 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: Annular Preventor Double Ram Rotating Head None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Beneficial reuse or land application plan submitted?

Reuse Facility ID: or Document Number:

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	65	0	60			
SURF	13+1/2	9+5/8	36	0	1001	829	1001	0
1ST	8+3/4	7	26	0	8610	893	8610	3000
1ST LINER	6+1/8	4+1/2	13.5	8410	15587			

Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number

OTHER LOCATION EXCEPTIONS

Check all that apply:

- Rule 318.c. Exception Location from Rule or Spacing Order Number
- Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

Best Management Practices

No	<u>BMP/COA Type</u>	<u>Description</u>
1	Planning	Multi-well Pads. It is a multi-well pad located in a manner which allows for resource extraction while maintaining the highest distances possible from the offsetting residential areas.
2	Traffic control	Access roads. The access road will be constructed to accommodate local emergency vehicles. This road will be maintained for access at all times.
3	General Housekeeping	Fencing requirements. A permanent fencing plan will be reviewed by the surface owner, & the applicant.
4	General Housekeeping	Removal of surface trash. All trash, debris and material not intrinsic to the operation of the oil and gas facility shall be removed and legally disposed of as is applicable.
5	Material Handling and Spill Prevention	Leak Detection Plan. Pumper will visit the location daily and visually inspect all tanks and fittings for leaks. Additionally, monthly documented SPCCP inspections are conducted pursuant to 40 CFR §112.
6	Material Handling and Spill Prevention	Berm construction. Tank berms shall be constructed of steel rings with a synthetic or engineered liner and designed to contain 150% of the capacity of the largest tank. All berms will be visually checked periodically to ensure proper working condition.
7	Material Handling and Spill Prevention	Load-lines. All load-lines shall be bull-plugged or capped.
8	Material Handling and Spill Prevention	Tank specifications. Tanks will be designed, constructed and maintained in accordance with NFPA Code 30. The tanks are visually inspected once a day for issues, and recorded inspections are conducted once a month.
9	Noise mitigation	Lighting abatement measures shall be implemented, including the installation lighting shield devices on all of the more conspicuous lights, & low density sodium lighting where practicable. At its election the operator may install temporary engineering controls consisting of perimeter sound walls shall be used on the location during drilling and completion activities to provide noise relief. Permanent equipment on location shall be muffled to reduce noise, or shall be appropriately buffered.
10	Drilling/Completion Operations	Closed Loop Drilling Systems – Pit Restrictions. Not applicable; a closed-loop system will be used for drilling.
11	Drilling/Completion Operations	Green Completions – Emission Control Systems. Test separators and associated flow lines and sand traps shall be installed on-site to accommodate Green completions techniques pursuant to COGCC Rules. In the anticipated absence of a viable gas sales line, the flow-back gas shall be thermally oxidized in an emissions control device (ECD), which will be installed and kept in operable condition for least the first 90-days of production pursuant to CDPHE rules. This ECD shall have an adequate capacity for 1.5 times the largest flow-back within a 10 mile radius, will be flanged to route gas to other or permanent oxidizing equipment and shall be provided with the equipment needed to maintain combustion where noncombustible gases are present.
12	Drilling/Completion Operations	Blowout preventer equipment (“BOPE”). A double ram and annular preventer will be used during drilling. At least the drilling company shall have a valid well blowout prevention certifications.
13	Drilling/Completion Operations	BOPE for well servicing operations. Adequate BOP equipment shall be used. Stabbing valves shall be installed in the event of reverse circulation and shall be prior tested with low and high pressure fluid.
14	Drilling/Completion Operations	Pit level indicators. Not applicable; a closed-loop system will be used and no pits shall be dug.
15	Drilling/Completion Operations	Drill stem tests. Not applicable; no Drill Stem tests are planned.
16	Drilling/Completion Operations	Control of fire hazards. All materials which are considered fire hazards shall be a minimum of 25' from the wellhead tanks or separators. Electrical equipment shall comply with API RP 500 and will comply with the current national electrical code. An emergency response plan has been generated for this site.
17	Drilling/Completion Operations	Guy line anchors. All guy line anchors shall be brightly marked pursuant to Rule 604.c (2)Q

18	Drilling/Completion Operations	Bradenhead Monitoring BMP: Operator will comply with COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
19	Drilling/Completion Operations	Anti-Collision BMP: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed wells. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.
20	Final Reclamation	Well site cleared. Within 90-day subsequent to the time of plugging and abandonment of the entire site, superfluous debris and equipment shall be removed from the site.
21	Final Reclamation	Identification of plugged and abandoned wells. P&A'd wells shall be identified pursuant to 319.a.(5).

Total: 21 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
1696478	PROPOSED SPACING UNIT
400407730	FORM 2 SUBMITTED
400624541	OffsetWellEvaluations Data
400624555	EXCEPTION LOC REQUEST
400624558	EXCEPTION LOC WAIVERS
400624559	WELL LOCATION PLAT
400624565	MINERAL LEASE MAP
400624568	SURFACE AGRMT/SURETY
400624572	DIRECTIONAL DATA
400624574	DEVIATED DRILLING PLAN

Total Attach: 10 Files

General Comments

User Group	Comment	Comment Date
Permit	Final Review Completed. Town of Greeley comment addressed (see OGLA comment on form 2); no public comment received.	2/10/2015 12:31:42 PM
OGLA	COGCC reviewed the City of Greeley USR for this location and the Operator submitted a Sundry (Doc #400691841) that was approved in September 2014 to add those BMPs that are appropriate and enforceable for this location.	2/9/2015 1:20:09 PM
Permit	ON HOLD: w/o Town of Greeley comment review.	1/29/2015 1:41:54 PM
Permit	Per operator changed Right to Construct from Oil & Gas lease to SUA. Removed Property line exception request. Received and attached a corrected Proposed Spacing unit map. Changed distance to nearest permitted or existing Wellbore Penetrating Objective Formation from 360' to 304'. Removed of Exception Location Request letter for Rules 604.a.(1)A & 604.a.(2). No Anti-Collision letter needed. Permitting Review Complete.	1/29/2015 1:41:53 PM
Permit	ON HOLD: Requesting change Right to Construct from Oil & Gas lease to SUA. Requesting Removal of Property line exception request. Requesting a corrected Proposed Spacing unit map. (The PSU attached has the surface location in section 24?). Requesting corrected distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in same formation. Requesting the corrected distance to nearest permitted or existing Wellbore Penetrating Objective Formation. Missing a Rule 318A.n Anti-Collision waiver. Corrected Exception Location Request letter for Rules 604.a.(1)A & 604.a.(2).	7/11/2014 2:16:00 PM
LGD	The City of Greeley has received, reviewed, and approved a Use by Special Review local land use permit for this expanded site. The USR (Planning File No. USR 1:14) was approved on April 22, 2014. The City of Greeley requests that, as part of the approval of the Form 2 Permit, all design and operational elements of the USR permit be honored, consistent, and incorporated. Please contact City staff for a copy of the approved and recorded Use by Special Review Permit, and please support the City requirement that this be available on-site for reference.	7/7/2014 1:55:22 PM
Engineer	Offset Wells Evaluated.	6/17/2014 9:21:44 AM
Permit	The comment period for this APD was extended per LGD request from 7/2/14 to 7/12/14.	6/13/2014 8:43:14 AM
Permit	Passed completeness.	6/12/2014 3:05:08 PM

Total: 9 comment(s)