

Noble Energy, INC
State 6525 #11-32
05-123-20367

Proposed Wellbore Schematic

Re-enter & replug
KB elev - 4680'
GL elev - 4670'

8.625" 24# surf csg @ 399'
w/280sxs cmt to surf

265sxs cmt from 700' to surface

Base Fox Hills 361'

Deepest Water Well 600'

100sxs cmt from 3000' to 2725'

Existing

50sxs cmt at 6530' (existing)

No Prod Csg
7.875" open hole to TD

TD = 6987'

Hunter Dunham
2/3/2015