



**\*NOTE:**

- 1.) 10% Swell Factor Applied to Earthwork Cut Volume.
- 2.) Topsoil Volume Based on 12" Soil Depth.
- 3.) Total Disturbed Area = ±4.81 ac.

**ESTIMATED EARTHWORK QUANTITIES (cy)**

ITEM	CUT	FILL	TOPSOIL	EXCESS
PAD	24780	12430	1600	10750
PIT	0			0
TOTALS	24780	12430	1600	10750

REVISED: 11/14/14

136 East Third Street  
Rifle, Colorado 81650  
Ph. (970) 625-2720  
Fax (970) 625-2773



**BOOKCLIFF**  
Survey Services, Inc.

SCALE: 1" = 80'  
DATE: 10/8/14  
PLAT: 2 of 7  
PROJECT: Valley  
DFT: cs

**Construction Plan Prepared for:**



WPX Energy Rocky Mountain, LLC

GM 14-27 Drill Pad - Plat 2

**Facility Layout Drawing**