

FORM
2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400780763

(SUBMITTED)

Date Received:

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Well Name: YATER

Well Number: 11B-17-07-95

Name of Operator: URS OPERATING COMPANY LLC

COGCC Operator Number: 10447

Address: 1050 17TH STREET #2400

City: DENVER

State: CO

Zip: 80265

Contact Name: JENNIFER LIND

Phone: (720)508-8362

Fax: ()

Email: JLIND@URSARESOURCES.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20120125

WELL LOCATION INFORMATION

QtrQtr: NWSW Sec: 17 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.435366

Longitude: -108.026402

Footage at Surface: 1792 feet

FNL/FSL

FSL

1128

feet

FEL/FWL

FWL

Field Name: PARACHUTE

Field Number: 67350

Ground Elevation: 5513

County: GARFIELD

GPS Data:

Date of Measurement: 09/26/2014

PDOP Reading: 1.2

Instrument Operator's Name: HOFFMANN

If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FNL/FWL

392

FNL

651

FWL

392

FNL

651

FWL

Sec: 17

Twp: 7S

Rng: 95W

Sec: 17

Twp: 7S

Rng: 95W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☒ is the mineral owner beneath the location.

(check all that apply) ☒ is committed to an Oil and Gas Lease.

☒ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: No

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

PLEASE SEE ATTACHED LEASE MAP.

Total Acres in Described Lease: 160 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 121 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 498 Feet
Building Unit: 498 Feet
High Occupancy Building Unit: 1578 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 847 Feet
Above Ground Utility: 867 Feet
Railroad: 5280 Feet
Property Line: 196 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone
☒ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 01/16/2015

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 329 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 392 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	440-58	240	Sec 17 NW, W/2NE

DRILLING PROGRAM

Proposed Total Measured Depth: 7842 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 329 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☐ Annular Preventor ☒ Double Ram ☐ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

See J(1) Waste Management Plan attached to 2A

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	84	0	60	111	60	0
SURF	12+1/4	8+5/8	32	0	1908	393	1908	0
1ST	7+7/8	4+1/2	11.6	0	7842	485	7842	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318A.a. Exception Location (GWA Windows).
- ☐ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments First String / Production cement will be > 500 feet above TOG. Distance to nearest well completed in the same formation / permitted or existing well penetrating objective formation was measured to the proposed Yater 11C-17-07-95.

Ursa requests the approval of a Rule 604.a.(1).B. exception location – request letter attached.

Pre-application Notice / Buffer Zone Notice was sent to building unit owners within 1000' of the location on 1/16/15. Pre-application certification is attached to the associated Yater Pad Form 2A Amendment (Doc #400778315).

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 159652

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: _____ Email: JLIND@URSARESOURCES.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Expiration Date: _____

API NUMBER

05

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	Open hole resistivity log with gamma ray will be run on a well on this pad to describe the stratigraphy of the vertical section of the wellbore and to adequately verify the setting depth of the surface casing and aquifer coverage. The Drilling Completion Report - Form 5 for every well on the pad will identify which well was logged.

Total: 1 comment(s)

Attachment Check List

Att Doc Num	Name
400790146	LEASE MAP
400790155	DEVIATED DRILLING PLAN
400790156	DIRECTIONAL DATA
400790163	EXCEPTION LOC REQUEST
400790635	WELL LOCATION PLAT
400791865	SURFACE AGRMT/SURETY

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

