

Bondad 33-10 #23

Current

Ignacio Blanco Mesaverde

1450' FSL & 1070' FEL, Section 15, T-33-N, R-10-W
La Plata County, CO / API #05-067-05459

Lat: 37.10028 / Long: -107.91607

Today's Date: 2/16/15
Spud: 7/10/62
Comp: 7/24/62
Elevation: 6316' GL

12.25" Hole

7" TOC @ 120' (T.S.)

9-5/8", 32.3#, H-40 Casing set @ 320'
210 sxs cement, circulated to surface,

Ojo Alamo @ 1780'

Kirtland @ 1944'

Fruitland @ 2285'

Pictured Cliffs @ 2758'

1-1/4" tubing at 5205'
(162 jts, 2.6#, J-55 EUE)

9.875" Hole

4.5" TOC @ 3040' (Liner Top)

7" 20#, J-55 Casing @ 3164'
Cemented with 345 sxs (407 cf)

Mesaverde @ 4974'

6.25" Hole

Mesaverde Perforations:
5190' - 5278'

4.5" 10.5, J-55 liner @ 5357'
Cemented with 220 sxs (387 cf)
Circulated out liner top.

TD 5359'
COTD 5290'