

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400794709

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 96850

Contact Name: GINA RANDOLPH

Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 260-4509

Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

API Number 05-045-21390-00

County: GARFIELD

Well Name: AP

Well Number: 422-20-695

Location: QtrQtr: NENW Section: 20 Township: 6S Range: 95W Meridian: 6

Footage at surface: Distance: 89 feet Direction: FNL Distance: 2511 feet Direction: FWL

As Drilled Latitude: 39.517416 As Drilled Longitude: -108.022889

GPS Data:

Date of Measurement: 11/27/2013 PDOP Reading: 3.3 GPS Instrument Operator's Name: J. KIRKPATRICK

** If directional footage at Top of Prod. Zone Dist.: 2045 feet. Direction: FNL Dist.: 1207 feet. Direction: FWL

Sec: 20 Twp: 6S Rng: 95W

** If directional footage at Bottom Hole Dist.: 2076 feet. Direction: FNL Dist.: 1175 feet. Direction: FWL

Sec: 20 Twp: 6S Rng: 95W

Field Name: PARACHUTE

Field Number: 67350

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 06/06/2014 Date TD: 06/16/2014 Date Casing Set or D&A: 06/17/2014

Rig Release Date: 06/17/2014 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 9333 TVD** 8860 Plug Back Total Depth MD 9275 TVD** 6880

Elevations GR 6909 KB 6935 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

RPM CBL MUDLOGS

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	108	40	0	108	VISU
SURF	13+1/2	9+5/8	32.3	0	2,698	670	0	2,698	VISU
1ST	8+3/4	4+1/2	11.6	0	9,318	950	5,448	9,318	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	3,934			NO	
MESAVERDE	6,175			NO	
CAMEO	8,956			NO	
ROLLINS	9,599			NO	

Comment:

Please note: The "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: GINA RANDOLPH

Title: PERMIT TECH II

Date: _____

Email: GINA.RANDOLPH@WPXENERGY.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400794757	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400794752	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400794722	PDF-CBL 1ST RUN	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400794728	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400794754	WELLBORE DIAGRAM	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400794760	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400794881	PDF-PULSED NEUTRON	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400794884	LAS-PULSED NEUTRON	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)