

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400800498

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100185

Contact Name: Erin Lind

Name of Operator: ENCANA OIL & GAS (USA) INC

Phone: (720) 876-5827

Address: 370 17TH ST STE 1700

Fax:

City: DENVER

State: CO

Zip: 80202-

API Number 05-123-36893-00

County: WELD

Well Name: Billings

Well Number: 3G-18H L368

Location: QtrQtr: NWSW Section: 18 Township: 3N Range: 68W Meridian: 6

Footage at surface: Distance: 1580 feet Direction: FSL Distance: 952 feet Direction: FWL

As Drilled Latitude: As Drilled Longitude:

GPS Data:

Date of Measurement: PDOP Reading: GPS Instrument Operator's Name:

** If directional footage at Top of Prod. Zone Dist.: 514 feet. Direction: FSL Dist.: 861 feet. Direction: FWL

Sec: 18 Twp: 3N Rng: 68W

** If directional footage at Bottom Hole Dist.: 396 feet. Direction: FSL Dist.: 2134 feet. Direction: FWL

Sec: 17 Twp: 3N Rng: 68W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 10/09/2014 Date TD: 12/17/2014 Date Casing Set or D&A: 12/18/2014

Rig Release Date: 12/30/2014 Per Rule 308A.b.

Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 14075 TVD** 7130 Plug Back Total Depth MD 14002 TVD** 7130

Elevations GR 5155 KB 5185 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

CBL, MWD. An open hole log omission request was granted for this pad.

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	16	65	0	156	160	0	156	CALC
SURF	12+1/4	9+5/8	40	0	1,004	407	0	1,020	CALC
1ST	8+3/4	7	26	0	7,520	672	0	7,540	CALC
2ND	6+1/8	4+1/2	13.5	0	14,054	619	5,553	14,075	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	7,039				
NIOBRARA	7,154				

Comment:

As-built coordinates were unable to be collected at this time due to the completions crew currently on site. These coordinates will be submitted via sundry as soon as possible.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Erin LindTitle: Regulatory Analyst

Date: _____

Email: erin.lind@encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?
-------------	---------------	------------

Attachment Checklist

400800511	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400800513	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>

Other Attachments

400800508	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400800509	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400800510	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400800515	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400800920	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)