

WPX Energy Rocky Mountain LLC

AP 423-17-695

PARACHUTE Field

SHL: 18' FNL 2485' FWL (NE/4 NW/4) Section 20 T6S R95W 6th PM

BHL: 1955' FSL 2200' FWL (NE/4 SW/4) Section 17 T6S R95W 6th PM

Garfield County Colorado

Formation Tops
(Measured Depths)

Conductor 26" Hole 18" casing/liner 62' W/ 23 Sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9-5/8" 32.3 ppf Csg. Set @ 2612'

In 13-1/2" Hole W/ 585 Sks. Cmt

Top Of Cement @ 5384'

"G" Sand @ 3775'

Mesaverde @ 6264'

Cameo @ 8937'

Rollins @ 9714'

Tubing String: 2-3/8" Set @ 9442'
On: 12.04.2014

7499-7689	Mesaverde
7728-7876	Mesaverde
7904-8060	Mesaverde
8098-8238	Mesaverde
8260-8386	Mesaverde
8408-8515	Mesaverde
8551-8753	Mesaverde
8789-8935	Mesaverde
8974-9167	Mesaverde
9200-9346	Mesaverde
9375-9504	Cameo
9526-9651	Lower Cameo

PBTD @ 9906'

TMD @ 9961'

TVD @ 9674'

4-1/2", 11.6 ppf. Csg. Set @ 9942' W/ 1005 Sks Cmt

DATE CREATED: 02.04.2015

NOTE: THIS IS NOT TO SCALE.

****FINAL****