

WPX Energy Rocky Mountain LLC

AP 424-17-695

PARACHUTE Field

SHL: 32' FNL 2488' FWL (NE/4 NW/4) Section 20 T6S R95W 6th PM

BHL: 493' FSL 2231' FWL (SE/4 SW/4) Section 17 T6S R95W 6th PM

Garfield County Colorado

Formation Tops
(Measured Depths)

Conductor 26" Hole 18" casing/liner 40' W/ 15 Sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9-5/8" 32.3 ppf Csg. Set @ 2544'

In 13-1/2" Hole W/ 575 Sks. Cmt

Top Of Cement @ 5048'

"G" Sand @ 3745'

Mesaverde @ 5975'

Cameo @ 8566'

Rollins @ 9363'

Tubing String: 2-3/8" Set @ 9088'
On: 12.02.2014

7139-7287	Mesaverde
7335-7496	Mesaverde
7541-7677	Mesaverde
7706-7826	Mesaverde
7855-8007	Mesaverde
8045-8220	Mesaverde
8250-8382	Mesaverde
8411-8558	Mesaverde
8603-8731	Mesaverde
8760-8950	Mesaverde
8975-9128	Cameo
9157-9311	Lower Cameo

PBTD @ 9490'

TMD @ 9555'

TVD @ 9524'

4-1/2", 11.6 ppf. Csg. Set @ 9534' W/ 1015 Sks Cmt

DATE CREATED: 2.4.2015

NOTE: THIS IS NOT TO SCALE.

****FINAL****