





Location ID 312614

Document 2314096

# COGIS - NOAV Report

## Operator Information

<b>DocNum:</b>	1120660	 <a href="#">Related</a>	 <a href="#">Docs by API</a>	 <a href="#">Single Doc</a>	 <a href="#">Docs under NOAV</a>
<b>Operator:</b>	VIRTEX PETROLEUM CO INC	<b>Date Rec'd:</b>	7/18/2002		
<b>Address:</b>	SUITE 525 MT 168 615 UPPER N BROADWAY CORPUS CHRISTI , TX 78477-				
<b>Company Rep.</b>		<b>Oper. No.</b>	93395		
<b>Well Name/No.</b>	BUZZARD CREEK 11-13	<b>Fac.Type:</b>	WELL		
<b>Location</b>	SWSW 11 T9S R93W 6	<b>County</b>	MESA		
<b>Fac.ID:</b>	222023	<b>Phone:</b>	()		
<b>API number:</b>	05-077 -08625				
<b>COGCC Rep:</b>	Jaime Adkins				

## Alleged Violation(s):

**Date of Alleged Violation:** 9/17/1998**Approx. time of violation:** 1:00:00 PM

SOIL ERROSION AND SUBSIDENCE IS OCCURRING AT THE WELL SITE DUE TO SITE CONSTRUCTION AND PIT CLOSURE PRACTICES. BENTONITE LEFT IN THE PIT HAS BEEN CREATED AN IMPERMEABLE LAYER PREVENTING NORMAL PRECIPITATION PERCOLATION. THE ADDITIONAL MOISTURE FROM THE DIVERTED PRECIPITATION IS CAUSING THE UNCONSOLIDATED ALLUVIUM TO BE UNSTABLE AND HAS RESULTED IS SIGNIFICANT ERROSION, SUBSIDENCE AND A LANDSLIDE AFFECTING 5-7 ACRES. IF ALLOWED TO CONTINUE THE WELLHEAD WILL BE DAMAGED CREATING A SAFETY HAZZARD.

## Act, Order, Regulation, Permit Conditions Cited:

RULE 1003.b., 1003.e.(2) AND 603.h.

## Abatement or Corrective Action Required to be Performed by Operator

STABILIZE THE SITE AND FILL SLOPE SOIL AND WELLHEAD. A SUGGESTION TO ACCOMPLISH THIS IS TO EXCAVATE THE IMPERMEABLE BENTONITE LAYER, INSTALL A FRENCH DRAIN TO REDUCE MOISTURE FLOW INTO THE ALLUVIUM, RE-CONTOUR AND REVEGETATE THE LOCAITON AND FILL SLOPE TO ALLEVIATE SUBSIDENCE, CONTROL ERROSION AND PREVENT WELLHEAD DAMAGE.

## Abatement or Corrective Action Required to be Completed by: 9/1/1999

*This section to be completed by Operator when alleged violation is corrected*

## Company Comments:

STABILIZED THE WELL SITE AND WELLHEAD. SLOPED AREA IN AD AROUND SITE AND WELL.

<b>Company Rep:</b>	BASIL PHIPPS	<b>Title:</b>	PRESIDENT
<b>Signature?</b>	Y	<b>Date:</b>	12/8/1998
<b>COGCC Signature? Y</b>		<b>Date:</b>	10/20/1998 3:00:00 PM
<b>Resolution approved by:</b>	JA	<b>Title:</b>	

## Final Resolution

<b>Date</b>	<b>Case Closed?</b>	<b>Letter Sent?</b>	<b>COGCC person</b>
12/18/1998	Y		Jaime Adkins

RECONTOURED, RE-SEEDED. WILL RE-CHECK NEXT AUGUST.

Friday, February 27, 2015