

OFFICE OF STATE OIL INSPECTOR  
SUNDRY NOTICES AND REPORTS OF WELLS  
LOCATED ON PRIVATE LANDS



(Indicate nature of data by checking below)

Notice of intention to drill X  
Notice of intention to change plans \_\_\_\_\_  
Notice of date for test of water shut-off \_\_\_\_\_  
Report on result of test of water shut-off \_\_\_\_\_  
Notice of intention to re-drill or repair well \_\_\_\_\_  
Notice of intention to clean out well \_\_\_\_\_  
Statement of shooting \_\_\_\_\_  
Statement of perforating \_\_\_\_\_  
Notice to pull or otherwise alter casing \_\_\_\_\_  
Notice of intention to abandon well \_\_\_\_\_  
Report of work done on well since previous report \_\_\_\_\_

Following is a (notice of intention to do work) (On land) Nov. 23 1951  
(~~report of work done~~) (patented) described as follows:

COLORADO	MORGAN	WILDCAT
State	County	Field
1 HOPE BISHOP	C-NE-NE-SW	
(Well No.) (Lease)	SW/4 SEC. 18	5N
	(Sec. and 1/4 Sec.)	(Twp.)
		58W
		(Range)
		(Meridian)

The well is located 990 ft. (N) of South Line and 330 ft. (E) of East  
Line, SW/4 Sec. 18

The elevation above sea level is 4799 ft. KB  
4786' ft. GL

Details of Plan of Work: (State names of and expected depths to objective sands;  
Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-  
ing points, and all other important proposed work.)

To drill and test subject well to the Morrison formation.

SURFACE CASING: 9-5/8" Nat'l. SS. to be set at 322' & cemented with 180 sax. Circulate  
cement to surface.

PRODUCTION STRING CASING: 5 1/2" O.D., 15 1/2#, J-55 casing to be set thru the potential  
producing formation. Casing point to be determined from geological data and electric  
log evaluation.

TESTING: 1. Diamond core "D" & "J" sands. 2. DST all significant shows.

LOGGING: One-run Schlumberger electric log from under surface casing to T.D. Run Micro-  
log on any indicated gas or oil zones.

DRIFT SURVEYS: At 50' intervals in surface hole and to a point 100' below surface casing,  
thereafter at 250' intervals.

DRILLING TIME: Use Geolograph.

SAMPLES: As directed by Geologists.

DEPTH MEASUREMENTS: S.L.M. of drill pipe at 4000' and prior to coring, DST and at T.D.

COMPLETION PROGRAM: To be determined by geological evaluation.

EXPECTED FORMATION TOPS: Niobrara 5251' - Ft. Hays 5517' - Greenhorn 5771' - "D" Sand  
5950' - "J" Sand 6008' - Morrison 6402'

Title Sup't., Northwestern District

DELIVERED TO THE STATE OF WYOMING BY THE UNITED STATES DEPARTMENT OF THE INTERIOR

Approved: DEC 4 1957

Company The British American Oil Producing Co.

J. J. Zouchak  
State Oil Inspector  
DIRECTOR

Address P. O. Box 620, Casper, Wyoming

By C. Wm. Evelyn, Jr.

Title Sup't., Northwestern District

Submit reports of proposed work, for approval, on this form in Duplicate.



~~087-46057~~  
087-06470