

Noble Energy, INC
Pfeiffer #16-26
05-123-13396

Proposed Wellbore Schematic

Status - DA
KB elev - 4633'
GL elev - 4623'

Plug: 200sxs from 500' to surface

Base Fox Hills 309'

8.625" 24#/ft surf csg set @ 320'
w/ 95sxs lite & 80sxs Class "G" to surface

Deepest Water well: 400'

Balanced Plug: 100sxs from 3000' to 2650'

Existing Balanced Plug: 25sxs @ 6300'

No Prod Csg
7.625" open hole to TD

TD = 6920'

EXISTING

Hunter Dunham
3/4/2015