

# NGL Water Solutions DJ, LLC

## **TDS CORRELATED BY FORMATION NAME**

### **NGL C6A**

API 05-123-40968

### **NGL C6**

API 05-123-26004

Formation	Top	Btm	TDS	Formation	Top	Btm	TDS
Lyons	9350'	9452'	16,960	Lyons	9004'	9148'	16,960
L. Satanka	9452'	9702'	13,526	L. Satanka	9334'	9408'	13,526
Wolfcamp	9702'	9748'	12,846	Wolfcamp	9412'	9461'	12,846
Amazon	9748'	9792'	12,846	Amazon	9461'	9512'	12,846
Council Grove	9792'	9948'	12,846	Council Grove	9512'	9642'	12,846
Admire	9948'	10050'					
Virgil	10050'	10218'					
Missouri	10218'	10270'					
Fountain	10270'	10540'					
Fountain Des Moines	10540'	10820'					
Fountain Atoka	10820'	10963'					

Incorrectly named in original SWD 1-30 mud log  
Lumped with Amazon on original SWD 1-30

Correlated by Formation: C6A TDS values from C6 for Lyons thru Council Grove

Admire thru Atoka Formations tested during completion operation of the C6A: results will be submitted with Final Permit