

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400807201

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100322

Contact Name: EILEEN ROBERTS

Name of Operator: NOBLE ENERGY INC

Phone: (303) 2284330

Address: 1625 BROADWAY STE 2200

Fax: (303) 2284286

City: DENVER State: CO Zip: 80202

API Number 05-123-39895-00

County: WELD

Well Name: Wells Ranch

Well Number: AE19-689

Location: QtrQtr: NWNW Section: 20 Township: 6N Range: 62W Meridian: 6

Footage at surface: Distance: 500 feet Direction: FNL Distance: 65 feet Direction: FWL

As Drilled Latitude: 40.478140 As Drilled Longitude: -104.355700

## GPS Data:

Date of Measurement: 12/31/2014 PDOP Reading: 2.6 GPS Instrument Operator's Name: Toa Sagapolutele

\*\* If directional footage at Top of Prod. Zone Dist.: 1 feet. Direction: FNL Dist.: 722 feet. Direction: FEL

Sec: 19 Twp: 6N Rng: 62W

\*\* If directional footage at Bottom Hole Dist.: 1 feet. Direction: FNL Dist.: 235 feet. Direction: FEL

Sec: 23 Twp: 6N Rng: 63W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 12/12/2014 Date TD: 12/21/2014 Date Casing Set or D&amp;A: 12/23/2014

Rig Release Date: 12/24/2014 Per Rule 308A.b.

## Well Classification:

☐ Dry ☐ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 17296 TVD\*\* 6709 Plug Back Total Depth MD 17279 TVD\*\* 6709

Elevations GR 4842 KB 4872 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

## List Electric Logs Run:

CBL/Mud/Gamma

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.05	30	130	80	0	130	VISU
SURF	13+3/4	9+5/8	36	30	749	303	0	749	VISU
1ST	8+3/4	7	26	30	6,941	589	750	6,491	CBL
1ST LINER	6+1/8	4+1/2	11.6	6929	17,281				

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	1,236				
PARKMAN	3,566				
SUSSEX	4,151				
SHANNON	4,910				
NIOBRARA	6,610				

Comment:

WAITING ON COMPLETION. THIS WELL WAS DRILLED BUT NOT YET REPORTED AS COMPLETED. THE TOP OF THE PRODUCING ZONE, AS REPORTED, IS TAKEN FROM THE ORIGINAL DRILLING PLAN. AT THE TIME OF COMPLETION, THE EXACT FOOTAGES WILL BE REPORTED. A MIT WILL BE DONE ON THE WELL WITHIN TWO YEARS OF TD IF THE WELL HAS NOT BEEN REPORTED AS COMPLETED.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Eileen Roberts

Title: Regulatory Analyst I

Date: \_\_\_\_\_

Email: eroberts@nobleenergyinc.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400807216	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400807217	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400807209	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400807210	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400807211	PDF-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400807213	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400807214	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400807215	LAS-MUD	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400807218	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)