

## **PROPOSED INJECTION PROGRAM**

### **NGL C6A:**

The NGL C6A well will take produced water from nearby oil & gas wells in Weld County. Water will be trucked to the Surface Facility #159193 located @ 1900' east where residual hydrocarbons and sediments will be removed before injection.

Under normal operating conditions, estimated fluid injection rates for produced water will be a minimum of 10,000 bbls per day @ 2200 psi to a maximum of 24,000 bbls per day @ 2500 psi. A Step Rate Test will be used to determine maximum injection pressure.

The above volumes are estimated for the single new well to be included in the adjacent Facility which will then service 2 separate UIC wells.