

**PROPOSED BMP's
XTO ENERGY, INC.**

**Certificate to Discharge Under CDPS General Permit No. COR-03000 Stormwater Discharges
Associated with Construction. Certification No. COR03C483**

- A Field Wide Stormwater Management Plan (SWMP) for the La Plata Infill Program is on file at the XTO Energy Inc. (72 Suttle Street, Suite J, Durango, CO, 81303) office. A Site Specific SWMP including a Site Plan will be developed for each location.
- Spill Prevention, Control and Countermeasures (SPCC) for the La Plata Infill Program is on file at the XTO Energy Inc. (72 Suttle Street, Suite J, Durango, CO, 81303) office. The Field Wide and Site Specific SWMPs each address SPCC during construction operations.
- Inspections of the project site and maintenance of installed BMP's shall be conducted in accordance with the CDPHE CDPS permit and field wide plan.
- The attached Table 1 lists BMP's which may be utilized during the construction phase and in development of the Site Specific SWMP. BMP selection is based on site specific conditions including topography, existing vegetation, timing, construction sequencing, etc.

Table 1

Stormwater Management BMPs		
Erosion Control BMPs (EC)	Sediment Control BMPs (SC)	Materials Handling and Spill Prevention BMPs (MH)
Seeding	Erosion Bale	Stockpile Management
Mulching	Erosion Logs	Material Management
Mulch Tackifier	Silt Fence	Material Use
Soil Binder	Storm Drain Inlet Protection	Spill Prevention and Control
Erosion Control Blankets	Sediment Trap	
Turf Reinforcement Mats	Sediment Basin	
Embankment Protector	Dewatering Structure	
Berm/Diversion	Stabilized Construction Entrance	
Check Dams	Brush Barrier	
Outlet Protection	Gravel Barrier	
Temporary Drainage Swale	Silt Barrier	
Grading Techniques		
Waste Management BMPs (WM)	General Pollution Prevention BMPs (GP)	Alternate (ALT) BMP's
Concrete Waste Management	Dewatering Operations	ALT 1 Run On Diverson
Solid Waste Management	Temporary Stream Crossing	ALT 2 Gabion Basket Outlet Protection
Sanitary and Septic Waste Management	Clear Water Diversion	ALT 3 Gabion Basket Retaining Wall
Liquid Waste Management	Non-Stormwater Discharge Management	ALT 4 Surface Crowning and Road Base/Gravel
Hazardous Waste Management	Wind Erosion Control	ALT 5 Armour
Contaminated Waste Management	Paving Operations	ALT 6 Sediment Control Device
	Street Sweeping and Vacuuming	ALT 7 Water Turnout
	Vehicle and Equipment Management	ALT 8 Bell Hole
		ALT 9 Permanent Slope Breakers (Water Bars)