

## Ft St Vrain 26 05-123-16910 - Planned WBD (P&A)

12-1/4" Surface Hole

7-7/8" Prod Hole

### Existing

KB: 4766'

GL: 4755'

8 5/8", 24# Sfc Csg set @ 511'

Fox Hills Marker 669'

Sussex productive within 1 mile: NO  
Shannon productive within 1 mile: NO

Sussex Top @ 4010'

TOC 6178' CBL

Niobrara Top @ 6792'

Niobrara perms 6793'-6872'

Codell perms 7080' - 7090'

4 1/2" 11.6 & 12.6# Prod Csg @ 7276'

TD @ 7222' 3/31/1993

### Planned

Welded Cap

Cement to surface

CIBP @ 80'

220 sk cmt plug 920' - 411'

Cut 4 1/2 csg off @ 820'

3660' TOC ID

Squeeze Perfs 3810'  
CICR

Squeeze Perfs 4210'

Cement Plug 25 sx 6740'-6340'

CIBP 6740'

Mud  
Existing Cement  
New Cement  
CIBP  
CICR

