

Dave Kubeczko - DNR

From: Dave Kubeczko - DNR
Sent: Friday, March 27, 2015 5:22 PM
To: dave.kubeczko@state.co.us
Subject: Elm Ridge Exploration Company LLC (Elm Ridge), IGE 132 Pad, SWNW Sec 11 T33N R8W, La Plata County, Form 2A#400649474

Categories: Operator Correspondence

Scan No 2107327 CORRESPONDENCE 2A#400649474

From: Terry Lindeman <TLindeman@elmridge.net>
Sent: Friday, March 27, 2015 3:22 PM
To: dave.kubeczko@state.co.us
Subject: Elm Ridge Exploration Company LLC (Elm Ridge), IGE 132 Pad, SWNW Sec 11 T33N R8W, La Plata County, Form 2A#400649474

Dave,
These are fine.
Thanks for the help.
Terry

From: Dave Kubeczko - DNR [mailto:dave.kubeczko@state.co.us]
Sent: Friday, March 20, 2015 4:57 PM
To: Terry Lindeman; jlr@animas.net
Subject: Elm Ridge Exploration Company LLC (Elm Ridge), IGE 132 Pad, SWNW Sec 11 T33N R8W, La Plata County, Form 2A#400649474

Terry,

I have been reviewing the Elm Ridge Exploration Company LLC (Elm Ridge) IGE 132 Pad **Form 2A** #400649474. COGCC would like to attach the following conditions of approval (COAs) to the Form 2A based on the data Elm Ridge has submitted on or attached to the Form 2A prior to passing the Oil and Gas Location Assessment (OGLA) review.

Planning: The following conditions of approval (COAs) will apply:

COA 91 - Notify the COGCC 48 hours prior to start of pad reconstruction/regrading (if necessary), rig mobilization, spud, pipeline testing, start of hydraulic stimulation operations, and start of flowback operations (if different than start of hydraulic stimulation operations) using Form 42 (the appropriate COGCC individuals will automatically be email notified, including the LGD for hydraulic stimulation operations).

Construction: The following conditions of approval (COAs) will apply:

COA 23 - Operator must ensure secondary containment for any volume of fluids contained at well site during drilling and completion operations; including, but not limited to, construction of a berm or diversion dike, diversion/collection trenches within and/or outside of berms/dikes, site grading, or other comparable measures (i.e., best management practices (BMPs) associated with stormwater management) sufficiently protective of nearby surface water. Any berm constructed at the well pad location will be stabilized, inspected at regular intervals (at least every 14 days per CDPHE requirements and after significant precipitation events), and maintained in good condition.

COA 44 - The access road will be maintained as to not allow any sediment to migrate from the access road to nearby surface water or any drainages leading to surface water.

COA 76 - Strategically apply fugitive dust control measures, including enforcing established speed limits on private roads, to reduce fugitive dust and coating of vegetation and deposition in water sources.

COA 58 - Berms or other containment devices shall be constructed to be sufficiently impervious (corrugated steel with poly liner) to contain any spilled or released material around permanent crude oil, condensate, and produced water storage tanks.

Drilling/Completions: The following conditions of approval (COAs) will apply:

COA 38 - The moisture content of any cuttings in a cuttings pit, trench, or pile shall be as low as practicable to prevent accumulation of liquids greater than de minimis amounts.

COA 25 - If the well is to be hydraulically stimulated, flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline or storage vessel located on the well pad; or into tanker trucks for offsite disposal. The flowback and stimulation fluid tanks, separators, or other containment/filtering equipment must be placed on the well pad in an area constructed to be sufficiently impervious to contain any spilled or released material.

COA 26 - Potential odors associated with the completions process and/or with long term production operations must be controlled/mitigated as to not impact nearby residences.

Material Handling and Spill Prevention: The following conditions of approval (COAs) will apply:

COA 45 - Operator shall pressure test pipelines in accordance with Rule 1101.e.(1) prior to putting into initial service any temporary surface or permanent buried pipelines and following any reconfiguration of the pipeline network.

COGCC would appreciate your concurrence with attaching these COAs to the Form 2A permit prior to passing the OGLA review. If you have any questions, please do not hesitate to call me at (970) 309-2514 (cell), or email. Thanks.

Dave

David A. Kubeczko, PG
Oil and Gas Location Assessment Specialist
Western Colorado



Colorado Oil & Gas Conservation Commission
Northwest Area Office
796 Megan Avenue, Suite 201
Rifle, CO 81650
FAX: (970) 625-5682
Cell: (970) 309-2514
dave.kubeczko@state.co.us | www.colorado.gov/cogcc

 *Please consider the environment before printing this e-mail*