

FORM

2

Rev
08/13

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109

Document Number:

400762298

APPLICATION FOR PERMIT TO:

☒ Drill
 ☐ Deepen
 ☐ Re-enter
 ☐ Recomplete and Operate

Date Received:

01/19/2015

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____Refilling ☐ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐Sidetrack ☐

Well Name: ICEMAN STATE

Well Number: 12N-16HZ

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

COGCC Operator Number: 47120

Address: P O BOX 173779

City: DENVER

State: CO

Zip: 80217-3779

Contact Name: Cheryl Light

Phone: (720)929-6461

Fax: (720)929-7461

Email: cheryl.light@anadarko.com

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: SWNW Sec: 15 Twp: 3N Rng: 67W Meridian: 6

Latitude: 40.227330

Longitude: -104.882655

Footage at Surface: 2030 feet
 FNL/FSL FNL 995 feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4798

County: WELD

GPS Data:

Date of Measurement: 09/04/2014 PDOP Reading: 2.1 Instrument Operator's Name: BART PFEIFER

If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**
 Footage at Top of Prod Zone: FNL/FSL FNL/FWL Bottom Hole: FNL/FSL FEL/FWL
 2222 FSL 566 FWL 2219 FSL 350 FWL
 Sec: 15 Twp: 3N Rng: 67W Sec: 16 Twp: 3N Rng: 67W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ IndianThe Surface Owner is: ☒ is the mineral owner beneath the location.(check all that apply) ☒ is committed to an Oil and Gas Lease.☐ has signed the Oil and Gas Lease.☒ is the applicant.The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: applicant is owner

Surface damage assurance if no agreement is in place:

Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

TOWNSHIP 3 NORTH, RANGE 67 WEST, 6TH P.M.
SECTION 15: NW
SECTION 22: S2SE, NWSE
WELD COUNTY, COLORADO
CONTAINING 280 ACRES

Total Acres in Described Lease: 280 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building: 1084 Feet
Building Unit: 1241 Feet
High Occupancy Building Unit: 5280 Feet
Designated Outside Activity Area: 5280 Feet
Public Road: 983 Feet
Above Ground Utility: 734 Feet
Railroad: 2869 Feet
Property Line: 602 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☐ Buffer Zone
☐ Exception Zone
☐ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

SPACING and UNIT INFORMATION

Distance from Completed Portion of Wellbore to Nearest Wellbore Permitted or Completed in the same formation: 57 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 738 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

UNIT CONFIGURATION: 03N-67W-SEC 15: NWSW, SWNW; SEC 16: N2S2, S2N2; SEC 17: NESE, SENE

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		480	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 12713 Feet

Distance to nearest permitted or existing wellbore penetrating objective formation: 53 Feet (Including plugged wells)

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? No

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Recycle/reuse

Cuttings Disposal: ONSITE Cuttings Disposal Method: Other

Other Disposal Description:

Please see Comments section. Disposal description will not fit in space provided.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	9+5/8	36	0	761	300	761	0
1ST	8+3/4	7	26	0	7348	750	7348	0
1ST LINER	6+1/8	4+1/2	11.6	6348	12713	460	12713	6448

☒ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____
- ☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments

OTHER DISPOSAL DESCRIPTION:

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent possible, at which point they will either be land applied or taken to a licensed, commercial disposal site; the decision will be based upon laboratory analysis of fluids.

Cuttings disposal: The surface owner has agreed to disposal of water-based cuttings onsite using bioremediation/solidification product.

This application is in a Comprehensive Drilling Plan _____ CDP #: _____

Location ID: 332749

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Mike McConaughy

Title: Sr Regulatory Analyst Date: 1/19/2015 Email: DJRegulatory@anadarko.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 3/30/2015

Expiration Date: 03/29/2017

API NUMBER

05 123 41342 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	<p>1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU.</p> <p>2) Comply with Rule 317.j and provide cement coverage from end of 7" casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.</p> <p>3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.</p>
	<p>Operator acknowledges the proximity of the listed wells. Operator agrees to provide mitigation Option 1 or 2 (per the DJ Basin Horizontal Offset Policy), ensure all applicable documentation is submitted, and submit a Form 42(s) ("OFFSET MITIGATION COMPLETED") for the remediated wells, referencing the API Number of the proposed horizontal well(s) stating what appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well.</p> <p>Richard Means GU 1 (API 123-08252) Mayer 22-15 (API 123-24686) State of Colorado AM 3 (API 123-14991) Davis State 20-16 (API 123-22247)</p>

Best Management Practices

No BMP/COA Type

Description

1	Planning	The nearest building unit is located 1,241' away from this oil and gas location, therefore it is not within a Designated Setback Location and is exempt from 604.c.
2	Drilling/Completion Operations	Kerr McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
3	Drilling/Completion Operations	<p>Prior to drilling operations, Operator may perform an anti-collision review of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision review may include MWD or gyro surveys and surface locations of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottom hole location. The proposed well may only be drilled if the anti-collision review results indicate that the risk of collision is sufficiently low as defined by the anti-collision plan, with separation factors greater than 1.5, or if the risk of collision has been mitigated through other means including shutting in wells, plugging wells, increased drilling fluid in the event of lost returns or as is appropriate for the specific situation. In the event of an increased risk of collision, that risk will be mitigated to prevent harm to people, the environment or property. For the proposed well, upon conclusion of drilling operations, an as-constructed directional survey will be submitted to COGCC with the Form 5.</p> <p>Please see the attached 318A.n letter for a list of well(s) identified by the operator as being within 150 feet of the proposed well(s). If no letter is attached, the operator has not identified any wells as being within 150 feet of the proposed well(s) at the time of permitting.</p>

Total: 3 comment(s)

Applicable Policies and Notices to Operators

Notice Concerning Operating Requirements for Wildlife Protection.

Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area.

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
2437445	ANTI-COLLISION WAIVER
400762298	FORM 2 SUBMITTED
400762974	DEVIATED DRILLING PLAN
400762975	WELL LOCATION PLAT
400762976	PROPOSED SPACING UNIT
400764578	DIRECTIONAL DATA
400770657	OFFSET WELL EVALUATION
400770658	OPEN HOLE LOGGING EXCEPTION
400770659	EXCEPTION LOC WAIVERS
400770660	SURFACE AGRMT/SURETY
400773725	EXCEPTION LOC REQUEST

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	3/30/2015 10:06:38 AM
Permit	Per operator changed lease description. to Lands Covered: Township 3 North, Range 67 West, 6th P.M. , Section 15: NW/4, Section 22: S/2SE/4, NW/4SE/4 & acres from 160 to 280 acres, more or less. Permit Review Complete.	3/30/2015 10:06:38 AM
Permit	ON HOLD: Requesting corrected lease description.	3/30/2015 10:06:37 AM
Engineer	Offset wells evaluated.	3/9/2015 2:35:12 PM
Permit	Permitting Review Complete.	2/25/2015 11:28:03 AM
Permit	Operator requested Exception to Open Hole Logging Rule 317.p. See attached.	2/25/2015 11:28:02 AM
Permit	Operator requests approval of an Anti-Collision Waiver for Rule 318A.n. Wellbore is to be located less than 150' from an existing wellbore. Request and waivers attached.	2/25/2015 11:28:01 AM
Permit	Passed Completeness	1/20/2015 3:19:40 PM

Total: 8 comment(s)