

Noble Energy, INC
UPRR 36 PAN AM B 1
05-123-07280

Proposed Wellbore Schematic

Re-enter and re-plug

KB elev - 4754'

GL elev - 4744'

PLUG: 50sxs cmt from 350' to surface

PLUG: CIBP set at 350'

Weld cap on 8 5/8" sur csg

8 5/8" sur csg set @ 406'
w/ 400 sks of cmt

Base Fox Hills 410'

Deepest Water well: 420'

PLUG: 50sxs cmt plug from 830' to 380'

100 sk cmt plug set @ 3000'

NO PROD CSG
open hole to TD

25 sk cmt plug set from 7340'-7430' (existing)

TD = 7580'