

## US ROCKIES REGION

## Anadarko Daily Summary Report

Well: UPRC FEDERAL 5-6K

Project: COLORADO-WELD-NAD83-UTM13

Site: UPRC FEDERAL 5-6K

Rig name no.: CONCORD 3/3

Event: ABANDONMENT

Start date: 3/10/2015

End date: 3/27/2015

Spud date: 4/13/1993

Active datum: RKB @4,789.99usft (above Mean Sea Level)

UWI: SE/NW/0/3/N/66/W/5/0/0/6/PM/N/2,368.00/W/0/2,439.00/0/0

| Report no. | Report date | MD (usft) | 24 hr summary   |
|------------|-------------|-----------|---|
| 1          | 03/10/2015  |           | MIRU, CONCORD RIG 3, BLOW DOWN WELL & CIRCULATED GAS OUT, ND WH NU BOP's, TALLY OUT 224 JTS 1 1/2 OUT OF THE HOLE, RU WL RIH W/ GAUGE RING TO 7230, PU CIBP FOR 2 7/8 CSG RIH SET IT @ 7185 RD WL, SWI SDFN.  |
| 2          | 03/11/2015  |           | RU HYDROTESTER TEST IN HOLE 212 JTS 1.5, CIR GAS OUT TRIED TO PRESSURE TEST CSG DID NOT HOLD, RU SANJEL PUMPED 20 SKS OF THERMAL 35, PUH TO 6340 CIRCULATED CLEAN, LD 5 JTS SWI SDFN.   |
| 3          | 03/12/2015  |           | TAG TOC @ 6360, TOO H LAYING DOWN 1 1/2 TUBING, RU WL RIH RUN CBL FROM 6350 TO SURFACE, PU JET CUTTER RIH CUT CSG @ 4310, ND BOP's UNLAND CSG NU, PULL 34 JTS WELL STARTED GASING SWI SDFN.   |
| 4          | 03/13/2015  |           | TOOH W/ 53 JTS, ND BOP's LD CASING PATCH, NU BOP, PULL 30 JTS, STARTED CIRCULATING WELL 8 JTS AT A TIME CIRCULATED DOWN TO 4240, DRAINED EQUIPMENT SWI SDFN.  |
| 5          | 03/16/2015  |           | TOOH, RU HYDROTESTER TEST IN 136 JTS 2 7/8, TAG FILL @ 4120 CIRCULATED DOWN TO 4405, RU SANJEL PUMPED 275 SX OF CLASS G, PUH TO 3600 CIRCULATED CLEAN W/ DRILLING MUD, LD 5 JTS SWI SDFN.   |
| 6          | 03/17/2015  |           | TAG TOC @ 3641, PUH LAYING DOWN TBG TO 1102, RU SANJEL PUMPED 260 SKS OF CONTROL SET C @ 13.5 END UP W/ 3 BBLS OF CMT BACK, TOO H LD TBG CLEAN EQUIP, WAIT ON CMT TO SET UP, RIH TAG TOC @ 86 ND BOP, RU WL SET 8.625 CIBP @ 80 PT TO 1000 PSI GOOD TEST, RDMO. |
| 7          | 03/27/2015  |           | Crew travel, safety. Dug up surface casing. Cut casing 6' below GL. Tagged @ 77'. Filled casing stub with 50 bags 5000# cement. Capped casing with a metal plate containing well info. Backfilled.  |
| 8          | 03/27/2015  |           | TIME : 13:30, ROUTE : N13, WINS: 22959, PROJECT TYPE: P&A, PROD: CD/NB, BATT#: 36144497, GATHERER: DCP, STATION: 213630, LINE : NA, COMMENTS: P&A'd OFFLINE.  |