



PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

1372
13260
INVOICE # 802543

TICKET NUMBER 47753
LOCATION Call 1st
FOREMAN Miles Shew

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12-10-14	A-40	C-18 #	V8	20S	69W	Fremont
CUSTOMER <u>Austin Exploration</u>			FLORNO CO			
MAILING ADDRESS			845			
CITY			STATE			
ZIP CODE			1146			
JOB TYPE <u>Surf</u>			HOLE SIZE <u>12 1/4"</u>			
CASING DEPTH <u>2513'</u>			HOLE DEPTH <u>2530</u>			
SLURRY WEIGHT <u>12.5/14.8</u>			SLURRY VOL <u>1.09/1.24</u>			
DISPLACEMENT <u>190 bbls</u>			DISPLACEMENT PSI <u>900/300</u>			
REMARKS: <u>Safety meetings and rig up on cross drilling. Circulate casing with air.</u>						
<u>Mix 6000 SX 65/35 Poz Cement with 68 gal 74 # Pos 13000 in with 150 SX</u>						
<u>Class A cement with 38 gal 28 gal Shut down Release plug displace 190</u>						
<u>bbls of water. @ 130 bbls displacement had 900 psi. Pressure fell to 300 psi.</u>						
<u>by 170 bbls Plug landed @ 1500 psi.</u>						
<u>Did not establish circulation before cementing</u>						
<u>Cement did not circulate</u>						
<u>Thanks Miles & crew</u>						

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401C	1	PUMP CHARGE	31.25 ⁰⁰	31.25 ⁰⁰
5406	175	MILEAGE	5.25	918.75
5407A	32.9 Tons	Ton mileage delivery	1.75	10075.62
5409	3	Per diem	250 ⁰⁰	750 ⁰⁰
1102	1800 #	Calcium Chloride	.94	1752.00
1107	150 #	Floccul / Celloflake	2.94	445.50
1118B	3096 #	Bentonite gel	.27	835.92
1127A	600 Sx	65/35 Poz Cement	16. ⁰⁰	9600 ⁰⁰
1104S	150 Sx	Class A Cement	18.55	2782.50
4133	6	9 5/8" Centralizer	98.75	592.50
4165	1	9 5/8" Ball & Spring Float shoe	863 ⁰⁰	863 ⁰⁰
4160	1	9 5/8" Float collar	924 ⁰⁰	924 ⁰⁰
4415	1	9 5/8" Buffer plug	199.50	199.50
4310	2	Thread lock compound	45 ⁰⁰	90 ⁰⁰
		Subtotal		33012.49
		15% 10% discount		3301.20
		Subtotal		39710.88
		SALES TAX		1245.68
		ESTIMATED TOTAL		30956.57

Ravin 3737

AUTHORIZATION John Akers TITLE VP Engineering DATE 12/17/14

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.