

ACCO-TERRA-STATE 24

SURFACE HOLE 12.25"

PRODUCTION HOLE 7.875"

* No BH pressure - From 17
28Oct14

Caliper avg from 41-4600' has
OH at 9.5' 12/11/72

Caliper avg at 6900' has OH at
9.0' 12/11/73

Existing

KB: 4,932
GL: 4,918

8 5/8" 24ppf H40 Sfc Csg set @ 805

Fox Hills Marker @ 1412

Sussex production w/in 1 mi **No**
Shannon production w/in 1 mi **No**
Deepest water well w/in 1 mi 872

Sussex Top @ 4390

Sussex Base @ 4616

New TOC 6460

CBL TOC 6680

Niobrara Top @ 6864

J Sand Perfs 7626-7764

4 1/2" 11.6 ppf K55 Prod Csg @ 7755

TD @ 7760 Spud 3/17/1973

Planned

Welded Cap
Cement to surface

CIBP @ 80

TOC ID @ 705

Cement Plug 435 sxs @ 1620 - 705

Cut 4 1/2" csg off @ 1520

TOC ID @ 4025
Top Perf 4190
CICR @ 4220

Cement Plug 190 sxs @ 4590 - 4190

Bottom Perf @ 4590

TOC ID @ 6685
Top Perf 6460
CICR @ 6490

Cement Plug @ 6660 - 6460

Bottom Perf @ 6660

CIBP @ 7570

