

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400811258

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: Kayla Hesseltine

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6552

Address: P O BOX 173779

Fax:

City: DENVER

State: CO

Zip: 80217-

API Number 05-123-38953-00

County: WELD

Well Name: BARCLAY

Well Number: 27C-11HZ

Location: QtrQtr: SWSE Section: 14 Township: 2N Range: 67W Meridian: 6

Footage at surface: Distance: 577 feet Direction: FSL Distance: 1679 feet Direction: FEL

As Drilled Latitude: 40.132399 As Drilled Longitude: -104.854600

GPS Data:

Date of Measurement: 11/11/2014

PDOP Reading: 2.0

GPS Instrument Operator's Name: Carli Sloan

** If directional footage at Top of Prod. Zone Dist.: 698 feet. Direction: FSL Dist.: 1264 feet. Direction: FEL

Sec: 14 Twp: 2N Rng: 67W

** If directional footage at Bottom Hole Dist.: 485 feet. Direction: FNL Dist.: 1300 feet. Direction: FEL

Sec: 11 Twp: 2N Rng: 67W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 11/07/2014 Date TD: 02/19/2015 Date Casing Set or D&A: 02/22/2015

Rig Release Date: 02/23/2015 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 17314 TVD** 7463 Plug Back Total Depth MD 17262 TVD** 7463

Elevations GR 4925 KB 4950

Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, GR, MUD

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0	953	379	0	953	VISU
1ST	8+3/4	7	26	0	7,945	697	0	7,945	CBL
1ST LINER	6+1/8	4+1/2	11.6	6946	17,310	695	6,946	17,310	CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,474				
SHARON SPRINGS	7,245				
NIOBRARA	7,329				
FORT HAYS	7,792				
CODELL	7,933				

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Kayla HesseltineTitle: Regulatory Specialist

Date: _____

Email: kayla.hesseltine@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400811267	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400811266	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400811262	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400811263	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400811264	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400811265	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400828772	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)