

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400810485

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: Kayla Hesseltine

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6552

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

API Number 05-123-39171-00

County: WELD

Well Name: GEE

Well Number: 2C-12HZ

Location: QtrQtr: NWNE Section: 24 Township: 2N Range: 67W Meridian: 6

Footage at surface: Distance: 771 feet Direction: FNL Distance: 1533 feet Direction: FEL

As Drilled Latitude: 40.128606 As Drilled Longitude: -104.835411

GPS Data:

Date of Measurement: 11/21/2014 PDOP Reading: 2.0 GPS Instrument Operator's Name: Carli Sloan

** If directional footage at Top of Prod. Zone Dist.: 139 feet. Direction: FSL Dist.: 1841 feet. Direction: FEL

Sec: 13 Twp: 2N Rng: 67W

** If directional footage at Bottom Hole Dist.: 486 feet. Direction: FNL Dist.: 2024 feet. Direction: FEL

Sec: 12 Twp: 2N Rng: 67W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 11/04/2014 Date TD: 02/11/2015 Date Casing Set or D&A: 02/13/2015

Rig Release Date: 02/23/2015 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 17665 TVD** 7403 Plug Back Total Depth MD 17614 TVD** 7403

Elevations GR 4859 KB 4875 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, GR, MUD

CASING, LINER AND CEMENT

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Top | Cmt Bot | Status |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|--------|
| SURF | 13+1/2 | 9+5/8 | 36 | 0 | 1,048 | 421 | 0 | 1,048 | VISU |
| 1ST | 8+3/4 | 7 | 26 | 0 | 7,789 | 760 | 36 | 7,789 | CBL |
| 1ST LINER | 6+1/8 | 4+1/2 | 11.6 | 6808 | 17,661 | 730 | 6,808 | 17,661 | CALC |

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

| Method used | String | Cementing tool setting/perf depth | Cement volume | Cement top | Cement bottom |
|-------------|--------|-----------------------------------|---------------|------------|---------------|
| | | | | | |

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

| FORMATION NAME | Measured Depth | | Check if applies | | COMMENTS (All DST and Core Analysis must be submitted to COGCC) |
|----------------|----------------|--------|------------------|-------|---|
| | Top | Bottom | DST | Cored | |
| SUSSEX | 4,372 | | | | |
| SHARON SPRINGS | 7,095 | | | | |
| NIOBRARA | 7,172 | | | | |
| FORT HAYS | 7,609 | | | | |
| CODELL | 7,701 | | | | |

Comment:

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Kayla HesseltineTitle: Regulatory Specialist

Date: _____

Email: kayla.hesseltine@anadarko.com

Attachment Check List

| Att Doc Num | Document Name | attached ? | | | |
|-----------------------------|--|------------|-------------------------------------|----|-------------------------------------|
| <u>Attachment Checklist</u> | | | | | |
| 400810509 | CMT Summary * | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | Core Analysis | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| 400810508 | Directional Survey ** | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | DST Analysis | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| | Logs | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | Other | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| <u>Other Attachments</u> | | | | | |
| 400810505 | PDF-MUD | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| 400810507 | DIRECTIONAL DATA | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| 400822423 | PDF-CEMENT BOND | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| 400828748 | LAS-MEASUREMENT/LOGGING WHILE DRILLING | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| 400828749 | PDF-MEASUREMENT/LOGGING WHILE DRILLING | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |

General Comments

User Group

Comment

Comment Date

| | | |
|--|--|--|
| | | |
|--|--|--|

Total: 0 comment(s)