

FORM
2A

Rev
08/13

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400472229

0

Date Received:

01/30/2015

Oil and Gas Location Assessment

☐ New Location ☒ Refile ☐ Amend Existing Location Location#: _____

Submit signed original form. This Oil and Gas Location Assessment is to be submitted to the COGCC for approval prior to any ground disturbance activity associated with oil and gas operations. Approval of this Oil and Gas Location Assessment will allow for the construction of the below specified Location; however, it does not supersede any land use rules applied by the local land use authority. Please see the COGCC website at <http://cogcc.state.co.us/> for all accompanying information pertinent this Oil and Gas Location Assessment.

Location ID:

441580

Expiration Date:

04/23/2018

☒ This location assessment is included as part of a permit application.

CONSULTATION

- ☐ This location is included in a Comprehensive Drilling Plan. CDP # _____
- ☐ This location is in a sensitive wildlife habitat area.
- ☐ This location is in a wildlife restricted surface occupancy area.
- ☐ This location includes a Rule 306.d.(1)A.ii. variance request.

Operator

Operator Number: 46290

Name: K P KAUFFMAN COMPANY INC

Address: 1675 BROADWAY, STE 2800

City: DENVER State: CO Zip: 80202

Contact Information

Name: Bill Yokley

Phone: (303) 814-0910

Fax: ()

email: byokley@kpk.com

RECLAMATION FINANCIAL ASSURANCE

☒ Plugging and Abandonment Bond Surety ID: 20010023 ☐ Gas Facility Surety ID: _____

☐ Waste Management Surety ID: _____

LOCATION IDENTIFICATION

Name: State _____ Number: #10-14

County: ARAPAHOE

QuarterQuarter: NWSE Section: 14 Township: 4S Range: 62W Meridian: 6 Ground Elevation: 5434

Define a single point as a location reference for the facility location. When the location is to be used as a well site then the point shall be a well location.

Footage at surface: 1974 feet FSL from North or South section line

1974 feet FEL from East or West section line

Latitude: 39.700640 Longitude: -104.291370

PDOP Reading: 6.0 Date of Measurement: 04/09/2009

Instrument Operator's Name: P. Steger

RELATED REMOTE LOCATIONS

(Enter as many Related Locations as necessary. Enter the Form 2A document # only if there is no established COGCC Location ID#)

This proposed Oil and Gas Location is:

LOCATION ID # FORM 2A DOC #

FACILITIES

Indicate the number of each type of oil and gas facility planned on location

Wells	<u>1</u>	Oil Tanks*	<u>1</u>	Condensate Tanks*	<u> </u>	Water Tanks*	<u>1</u>	Buried Produced Water Vaults*	<u> </u>
Drilling Pits	<u> </u>	Production Pits*	<u> </u>	Special Purpose Pits	<u> </u>	Multi-Well Pits*	<u> </u>	Modular Large Volume Tanks	<u> </u>
Pump Jacks	<u>1</u>	Separators*	<u>1</u>	Injection Pumps*	<u> </u>	Cavity Pumps*	<u> </u>	Gas Compressors*	<u>1</u>
Gas or Diesel Motors*	<u> </u>	Electric Motors	<u> </u>	Electric Generators*	<u> </u>	Fuel Tanks*	<u> </u>	LACT Unit*	<u> </u>
Dehydrator Units*	<u> </u>	Vapor Recovery Unit*	<u> </u>	VOC Combustor*	<u>1</u>	Flare*	<u> </u>	Pigging Station*	<u> </u>

OTHER FACILITIES*

Other Facility Type

Number

Those facilities indicated by an asterisk () shall be used to determine the distance from the Production Facility to the nearest cultural feature on the Cultural Setbacks Tab.

Per Rule 303.b.(3)C, description of all oil, gas, and/or water pipelines:

1 Oil pipeline, 1 Gas pipeline, 1 Water pipeline.

CONSTRUCTION

Date planned to commence construction: 12/01/2015 Size of disturbed area during construction in acres: 2.00
Estimated date that interim reclamation will begin: 02/05/2016 Size of location after interim reclamation in acres: 0.50
Estimated post-construction ground elevation: 5434

DRILLING PROGRAM

Will a closed loop system be used for drilling fluids: Yes
Is H₂S anticipated? No
Will salt sections be encountered during drilling: No
Will salt based mud (>15,000 ppm Cl) be used? No
Will oil based drilling fluids be used? No

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Method: Land application
Cutting Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal
Other Disposal Description:

Beneficial reuse or land application plan submitted? No

Reuse Facility ID: or Document Number:

Centralized E&P Waste Management Facility ID, if applicable:

SURFACE & MINERALS & RIGHT TO CONSTRUCT

Name: State of Colorado Phone:

Address: 1313 Sherman St.

Fax: _____

Address: _____

Email: _____

City: Denver State: CO Zip: 80203-2244

Surface Owner: ☐ Fee ☒ State ☐ Federal ☐ Indian

Check all that apply. The Surface Owner: ☒ is the mineral owner

☒ is committed to an oil and Gas Lease

☒ has signed the Oil and Gas Lease

☐ is the applicant

The Mineral Owner beneath this Oil and Gas Location is: ☐ Fee ☒ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed from or produced to this Oil and Gas Location: Yes

The right to construct this Oil and Gas Location is granted by: oil and gas lease

Surface damage assurance if no agreement is in place: Blanket Surface Surety ID: 20010024

Date of Rule 306 surface owner consultation 09/23/2009

CURRENT AND FUTURE LAND USE

Current Land Use (Check all that apply):

Crop Land: ☐ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☒ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): _____

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

Future Land Use (Check all that apply):

Crop Land: ☐ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☒ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): _____

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

CULTURAL DISTANCE INFORMATION

Provide the distance to the nearest cultural feature as measured from Wells or Production Facilities onsite.

	From WELL	From PRODUCTION FACILITY
Building:	3737 Feet	3737 Feet
Building Unit:	4124 Feet	4124 Feet
High Occupancy Building Unit:	5280 Feet	5280 Feet
Designated Outside Activity Area:	5280 Feet	5280 Feet
Public Road:	3832 Feet	3832 Feet
Above Ground Utility:	3639 Feet	3639 Feet
Railroad:	5280 Feet	5280 Feet
Property Line:	1974 Feet	1974 Feet

INSTRUCTIONS:

- All measurements shall be provided from center of nearest Well or edge of nearest Production Facility to nearest of each cultural feature as described in Rule 303.b.(3)A.
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.
- For measurement purposes only, Production Facilities should only include those items with an asterisk(*) on the Facilities Tab.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:

☐ Buffer Zone

☐ Exception Zone

☐ Urban Mitigation Area

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit.
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: _____

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: _____

FOR MULTI-WELL PADS AND PRODUCTION FACILITIES WITHIN DESIGNATED SETBACK LOCATIONS ONLY:

- ☐ Check this box if this Oil and Gas Location has or will have Production Facilities that serve multiple wells (onll or offsite) and the Production Facilities are proposed to be located less than 1,000 feet from a Building Unit. *(Pursuant to Rule 604.c.(2)E.i., the operator must evaluate alternative locations for the Production Facilities that are farther from the Building Unit, and determine whether those alternative locations were technically feasible and economically practicable for the same proposed development.)*
- ☐ By checking this box, I certify that no alternative placements for the Production Facilities, farther from the nearest Building Unit, were available based on the analysis conducted pursuant to Rule 604.c.(2)E.i.

In the space below, explain rationale for siting the multi-well Production Facility(ies) that supports your Rule 604.c.(2)E.i determination. Attach documentation that supports your determination to this Form 2A.

SOIL

List all soil map units that occur within the proposed location. attach the National Resource Conservation Service (NRCS) report showing the "Map Unit Description" report listing the soil typical vertical profile. This data is to be used when segregating topsoil.

The required information can be obtained from the NRCS web site at <http://soildatamart.nrcs.usda.org/> or from the COGCC web site GIS Online map page found at <http://colorado.gov/cogcc>. Instructions are provided within the COGCC web site help section.

NRCS Map Unit Name: Weld Silt Loam, 0 to 3 percent slopes - WeB

NRCS Map Unit Name: Samsil-Renohil clay loams, 3 to 20 percent slopes - SrE

NRCS Map Unit Name: _____

PLANT COMMUNITY:

Complete this section only if any portion of the disturbed area of the location's current land use is on non-crop land.

Are noxious weeds present: Yes ☐ No ☒

Plant species from: ☐ NRCS or, ☒ field observation Date of observation: 10/02/2013

List individual species:

Check all plant communities that exist in the disturbed area.

- ☒ Disturbed Grassland (Cactus, Yucca, Cheatgrass, Rye)
☐ Native Grassland (Bluestem, Grama, Wheatgrass, Buffalograss, Fescue, Oatgrass, Brome)
☐ Shrub Land (Mahogany, Oak, Sage, Serviceberry, Chokecherry)
☐ Plains Riparian (Cottonwood, Willow, Aspen, Maple, Poplar, Russian Olive, Tamarisk)
☐ Mountain Riparian (Cottonwood, Willow, Blue Spruce)
☐ Forest Land (Spruce, Fir, Ponderosa Pine, Lodgepole Pine, Juniper, Pinyon, Aspen)
☐ Wetlands Aquatic (Bullrush, Sedge, Cattail, Arrowhead)
☐ Alpine (above timberline)
☐ Other (describe):

WATER RESOURCES

Is this a sensitive area: ☒ No ☐ Yes

Distance to nearest

downgradient surface water feature: 543 Feet

water well: 2200 Feet

Estimated depth to ground water at Oil and Gas Location 13 Feet

Basis for depth to groundwater and sensitive area determination:

Location lies within a Sensitive Area due to potential shallow groundwater. Location lies within the North Kiowa Bijou Designated Groundwater Management Area and Kiowa Bijou Designated Basin.

Estimated Depth to Groundwater based on DWR Permit #86681

Is the location in a riparian area: ☒ No ☐ Yes

Was an Army Corps of Engineers Section 404 permit filed ☒ No ☐ Yes If yes attach permit.

Is the location within a Rule 317B Surface Water Supply Area buffer No

zone:

If the location is within a Rule 317B Surface Water Supply Area buffer have all public water supply systems within 15 miles been notified: No

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 609

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
☐

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments	<p>No improvements are located within 500 feet of the proposed Location</p> <p>This is a refile of a permit approved on 12-04-2009. Doc. No. 1692808, Loc ID 414718.</p> <p>No conductor casing.</p> <p>There have been no changes in land use. Distance to nearest well permitted/completed in same formation is different than previous Form 02 and the distance to nearest building, public road, above ground utility is different than previous Form 02 as well. Location ID: 414718.</p> <p>I certify that there have been no changes on land use or lease description.</p> <p>The pad has not been built.</p> <p>The pit will not be used.</p> <p>There will be no additional surface disturbance from originally approved permit.</p> <p>The location does not require a variance from any of the rules listed in Rule 306.d.(1).(ii).</p> <p>The location is not within a wildlife Restricted Surface Occupancy Area.</p> <p>LGD comments on the previously approved APD.</p>
----------	--

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.

Signed: _____ Date: 01/30/2015 Email: slaramesa@kpk.com

Print Name: Susana Lara-Mesa Title: Engineering Project Mgr.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  _____ Director of COGCC Date: 4/24/2015

Conditions Of Approval

All representations, stipulations and conditions of approval stated in this Form 2A for this location shall constitute representations, stipulations and conditions of approval for any and all subsequent operations on the location unless this Form 2A is modified by Sundry Notice, Form 4 or an Amended Form 2A.

COA Type	Description
	Operator shall provide notice to COGCC 48 hours prior to commencing construction of this Oil and Gas Location via Form 42.
	The proposed location lies within a sensitive area with potential shallow groundwater and within proximity to a surface water drainage. In addition, the proposed location lies within the North Kiowa Bijou Designated Groundwater Management Area and Kiowa Bijou Designated Basin. Secondary containment areas for tanks shall be constructed of steel rings, designed and installed to prevent leakage and resist degradation from erosion or routine operation and shall be constructed with a synthetic or engineered liner that contains all primary containment vessels and flowlines and is mechanically connected to the steel ring to prevent leakage. In addition, tertiary containment shall be constructed around the down and cross-gradient perimeters of the Location.

Best Management Practices

<u>No</u>	<u>BMP/COA Type</u>	<u>Description</u>
1	General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite suitable facilities according to WMP. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal at a certified facility. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each workday. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, any contaminated soil, and dust control on location. Materials will be disposed of properly.
2	Storm Water/Erosion Control	Storm water Management Plan (SWMP) will be in place to address construction, drilling and operations associated with oil and gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit rules. BMP's used will vary according to location, and will remain in place until the pad reached final reclamation.
3	Material Handling and Spill Prevention	Spill Prevention Control and countermeasure plan (SPCC) is in place to address construction, drilling and operations associated with oil and gas development throughout the state of Colorado in accordance with CFR 112.
4	Drilling/Completion Operations	Pre-Spud Anti-collision Prior to drilling operations, operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to the COGCC with the Form 5.
5	Drilling/Completion Operations	During and Post Stimulation K.P. Kauffman, Inc. will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012. At least 90 days prior to fracture stimulation, the Operator shall notify all operators of non-operated wells within 1500' of the wellbore to be fracture stimulated of the anticipated stimulation date and the recommended best management practice to shut-in all wells within 1500' of the stimulated wellbore completed in the same formation. The Operator will monitor bradenhead pressure of all wells under Operator's control within 300 feet of the well which is to be treated, provided such other wells penetrate the productive zone which is to be treated.

Total: 5 comment(s)

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
1009790	CORRESPONDENCE
400472229	FORM 2A SUBMITTED

Total Attach: 2 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	4/22/2015 8:31:49 AM
OGLA	Changed Centralized E&P Facility to Commercial Disposal per Operator request. Added the statement "No improvements are located within 500 feet of the proposed Location" under Submit tab per Operator request.	3/24/2015 11:52:15 AM
OGLA	Added "Samsil-Renohil clay loams, 3 to 20 percent slopes - SrE" to the Soils Section Re-wrote "Weld Silt Loam, 0 to 3 percent slopes - WeB" in the Soils Section	3/24/2015 10:31:04 AM
OGLA	Changed the Sensitive Area to YES based on the Designated Groundwater Management Area, Designated Basin and potential shallow groundwater (at 13 feet). Changed Depth to Groundwater to 13 feet. Added the statement "Location lies within a Sensitive Area due to potential shallow groundwater. Location lies within the North Kiowa Bijou Designated Groundwater Management Area and Kiowa Bijou Designated Basin" to the Basis Statement. Added "Estimated Depth to Groundwater based on DWR Permit #86681"	3/5/2015 5:46:20 PM
Permit	Surface Restoration Bond on file with SLB; per SLB.	2/25/2015 11:37:26 AM
Permit	Emailed SLB for verification of Surface Restoration Bond and mineral lease.	2/5/2015 11:43:45 AM
Permit	Per operator, corrected interim reclamation date from 2/5/2015 to 2/5/2016. Passed completeness.	2/3/2015 9:48:51 AM

Total: 7 comment(s)