

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400831622

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10447

Contact Name: JENNIFER LIND

Name of Operator: URSA OPERATING COMPANY LLC

Phone: (720) 508-8362

Address: 1050 17TH STREET #2400

Fax:

City: DENVER

State: CO

Zip: 80265

API Number 05-045-22424-00

County: GARFIELD

Well Name: BAT

Well Number: 34C-24-07-96

Location: QtrQtr: NESW Section: 24 Township: 7S Range: 96W Meridian: 6

Footage at surface: Distance: 1830 feet Direction: FSL Distance: 2031 feet Direction: FWL

As Drilled Latitude: 39.420644 As Drilled Longitude: -108.060116

## GPS Data:

Date of Measurement: 02/26/2015 PDOP Reading: 1.5 GPS Instrument Operator's Name: Aibner

\*\* If directional footage at Top of Prod. Zone Dist.: 695 feet. Direction: FSL Dist.: 2027 feet. Direction: FEL

Sec: 24 Twp: 7S Rng: 96W

\*\* If directional footage at Bottom Hole Dist.: 698 feet. Direction: FSL Dist.: 2027 feet. Direction: FEL

Sec: 24 Twp: 7S Rng: 96W

Field Name: WILDCAT

Field Number: 99999

Federal, Indian or State Lease Number: COC027825

Spud Date: (when the 1st bit hit the dirt) 09/19/2015 Date TD: 02/20/2015 Date Casing Set or D&amp;A: 02/21/2015

Rig Release Date: 02/22/2015 Per Rule 308A.b.

## Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 6088 TVD\*\* 5645 Plug Back Total Depth MD 6035 TVD\*\* 5592

Elevations GR 5182 KB 5195 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

## List Electric Logs Run:

CBL, MUD, PULSED NEUTRON. OPEN HOLE LOGS WERE PREVIOUSLY RUN ON 2 WELLS ON THIS PAD: BAT 12B-24-07-96 (05-045-20562) AND BAT 23CWI-24-07-96 (05-045-22313)

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	75	0	73	70	0	73	CALC
SURF	12+1/4	8+5/8	32	0	1,908	465	0	1,924	CALC
1ST	7+7/8	4+1/2	11.6	0	6,080	706	2,290	6,088	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	3,036		NO	NO	
CAMEO	5,489		NO	NO	
ROLLINS	6,010		NO	NO	

Comment:

LAT / LONGS PROVIDED IN THE WELL INFORMATION SECTION ARE ACTUAL, AS DRILLED COORDINATES. AS DRILLED PLAT IS ATTACHED FOR YOUR REFERENCE.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: JENNIFER LIND

Title: REGULATORY ANALYST

Date: \_\_\_\_\_

Email: JLIND@URSARESOURCE.COM

## Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400832551	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400832542	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400832529	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400832534	PDF-PULSED NEUTRON	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400832535	LAS-PULSED NEUTRON	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400832539	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400832548	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400832553	WELL LOCATION PLAT	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

### General Comments

User Group

Comment

Comment Date

--	--	--

Total: 0 comment(s)