

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400811509

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 100322

Contact Name: EILEEN ROBERTS

Name of Operator: NOBLE ENERGY INC

Phone: (303) 2284330

Address: 1625 BROADWAY STE 2200

Fax: (303) 2284286

City: DENVER State: CO Zip: 80202

API Number 05-123-40161-00

County: WELD

Well Name: Crow Creek

Well Number: AA01-743

Location: QtrQtr: NWNE Section: 1 Township: 6N Range: 63W Meridian: 6

Footage at surface: Distance: 290 feet Direction: FNL Distance: 2238 feet Direction: FEL

As Drilled Latitude: 40.522072 As Drilled Longitude: -104.382894

GPS Data:

Date of Measurement: 11/17/2014 PDOP Reading: 2.2 GPS Instrument Operator's Name: Toa Sagapolutele

** If directional footage at Top of Prod. Zone Dist.: 618 feet. Direction: FNL Dist.: 2166 feet. Direction: FEL

Sec: 1 Twp: 6N Rng: 63W

** If directional footage at Bottom Hole Dist.: 30 feet. Direction: FNL Dist.: 2165 feet. Direction: FEL

Sec: 12 Twp: 6N Rng: 63W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 01/25/2015 Date TD: 01/30/2015 Date Casing Set or D&A: 02/01/2015

Rig Release Date: 02/02/2015 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 11906 TVD** 6716 Plug Back Total Depth MD 11812 TVD** 6716

Elevations GR 4833 KB 4857 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

CBL/Mud/Gamma. Pad Ref. Well=Crow Creek AA 01-756

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.5	24	124	60	0	124	VISU
SURF	13+1/2	9+5/8	36	24	2,248	750	0	2,248	VISU
1ST LINER	6+1/8	5+1/2	11.6	24	11,902	1,545	1,515	11,902	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PIERRE	1,138				
PARKMAN	3,627				
SUSSEX	4,410				
SHANNON	4,969				
NIOBRARA	6,566				

Comment:

WAITING ON COMPLETION. THIS WELL WAS DRILLED BUT NOT YET REPORTED AS COMPLETED. THE TOP OF THE PRODUCING ZONE, AS REPORTED, IS TAKEN FROM THE ORIGINAL DRILLING PLAN. AT THE TIME OF COMPLETION, THE EXACT FOOTAGES WILL BE REPORTED. A MIT WILL BE DONE ON THE WELL WITHIN TWO YEARS OF TD IF THE WELL HAS NOT BEEN REPORTED AS COMPLETED.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts _____

Title: Regulatory Analyst I _____ Date: _____ Email: eroberts@nobleenergyinc.com _____

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
400834127	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
400812975	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
400812973	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400812976	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400812977	PDF-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400812979	PDF-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400812980	LAS-GAMMA RAY	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400812984	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
400812987	PDF-GAMMA RAY	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)