



# **DRILLING COMPANY, INC.** **WICHITA, KANSAS**

## **Current Wellbore Configuration**

|            |                      |
|------------|----------------------|
| Date:      | 5/1/2015             |
| Well Name: | NWAU #10             |
| Location:  | SW NE                |
|            | Section 36-T13S-R43W |
| County:    | Cheyenne             |
| State:     | Colorado             |
| API:       | 05-017-06979         |
| KB:        | 4024'                |
| GL:        | 4012'                |
| Spud Date: | 3/7/1989             |

**Note: Original well name was the State-Arends #3**

Casing leak between 2777' and 2808' squeezed with 88 sks. cement (9/91)

2-7/8" tubing set at 5279'

Top of cement at 5056' (CBL 3/20/1989)

Peforations in Morrow at 5247'-5252' (88 holes)

5-1/2", 15.5# csg set at 5418'  
 Cmt w/100 sks. Class A