

Noble Energy, INC
Bringelson #1-28
05-123-14707

Current Wellbore Schematic

Status - DA
KB elev - 4866'
GL elev - 4856'

8.625" 24#/ft surf csg set @ 308'
w/185sxs cmt to surface

10sxs cmt at surf

Balanced Plug: 35sxs 271'/341'

Base Fox Hills 633'

Deepest Water well: 1170'

No Prod Csg
7.875" open hole to TD

TD = 6641'

Hunter Dunham
3/17/2015