

Noble Energy, INC  
Bringelson #1-28  
05-123-14707

**Proposed Wellbore Schematic**

Status - DA  
KB elev - 4866'  
GL elev - 4856'

8.625" 24#/ft surf csg set @ 308'  
w/185sxs cmt to surface

Balanced Plug: 280 sxs 750' to surface

Base Fox Hills 633'

Deepest Water well: 1170'

Balanced Plug: 110 sxs 1000'/1300'

Balanced Plug: 75 sxs 2500'/2700'

No Prod Csg  
7.875" open hole to TD

TD = 6641'

Hunter Dunham  
3/17/2015